

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-19075-00-00
Spot: NWNENE Sec/Twnshp/Rge: 31-14S-14W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: SOLBACH NORTH #1 & #2 LE Well #: 2
County: RUSSELL Total Vertical Depth: 3150 feet

Operator License No.: 34318

String Size Depth (ft) Pulled (ft) Comments

Op Name: BEREXCO LLC

L1 5.5 3150 250 sx

Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

PROD 7 2952 25 SX

SURF 10 785 25 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/11/2017 10:30 AM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Rcvd. from: DENNIS KIRMER

Company: BEREXCO LLC

Phone: (316) 772-6449

Proposed
Plugging
Method:

Ordered 425 sx 60/40 pozmix 4% gel cement w/600 # hulls and 400 # gel (4 sx).

Plugging Proposal Received By: RAY DINKEL

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/11/2017 3:30 PM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 320', 765' and 1400'. Ran tubing to 2950' and pumped 400 # gel followed by 100 sx cement w/200 # hulls mixed in the last half of cement. Pulled tubing to 1425' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 430' and pumped 45 sx cement. Circulated cement to pit. POOH. Hooked to casing and pumped 5 sx cement to 300 psi. Hooked to braden head and pressured to 350 psi.

GPS: 38.79749 -098.915399

Perfs:

Top	Bot	Thru	Comments
3150	3162		

KCC WICHITA
JAN 24 2017
RECEIVED

Remarks: QUALITY CASING SERVICE TICKET # 001

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

JAN 12 2017

Form CP-2/3