

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-00067-00-02
Spot: NWSWSWNW Sec/Twashp/Rge: 21-32S-3E
3111 feet from S Section Line, 5010 feet from E Section Line
Lease Name: BURSACK Well #: 2-21
County: COWLEY Total Vertical Depth: 2279 feet

Operator License No.: 30169
Op Name: DOUBLE "D" OIL COMPANY, INC.
Address: 2009 JEAN CT
WINFIELD, KS 67156

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|--|
| PKR | | 2149 | | PACKER TYPE AND SETTING DEPTH: AD-1 SET @ 2149' |
| PROD | 5.5 | 2312 | | 250 SX |
| SURF | 8.625 | 89 | | 80 SX |
| T1 | 2.375 | 2149 | | |

Well Type: SWD UIC Docket No: D28613.0 Date/Time to Plug: 12/27/2016 8:00 AM
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING
Proposal Rcvd. from: DONALD L BUTLER Company: DOUBLE D OIL CO Phone: (620) 221-3570

Proposed Plugging Method: AS PER KCC RULES & REGS / CMT 50' ABOVE TOP PERF, CIRC 350'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 12/28/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2254', MCPHERSON DRILLING MIXED & PUMPED 20 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 2120'. RIH W/TBG @ 350'. MCPHERSON DRILLING ESTABLISHED CIRCULATION, MIXED & PUMPED 40 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. LAYED DOWN TUBING. TOPPED WELL BACK TO SURFACE W/7 SXS CLASS A COMMON.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2228 | 2254 | CSG | |
| 2190 | 2216 | CSG | |

Remarks: CEMENT @ SURFACE ON BACKSIDE 5-1/2" CASING

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

INVOICED
JAN 24 2017