

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-033-21448-00-00  
 Spot: NW Sec/Twnshp/Rge: 9-35S-16W  
3969 feet from S Section Line, 4016 feet from E Section Line  
 Lease Name: LINDA SUE Well #: 1-9  
 County: COMANCHE Total Vertical Depth: 5600 feet

Operator License No.: 34434  
 Op Name: EDISON OPERATING COMPANY LLC  
 Address: 8100 E. 22ND ST. N., BLDG 1900  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4880		WITH 2 SX CMT
CIBP		5100		
CIBP		5250		
PROD	4.5	5572	3810	WITH 270 SX CMT
SURF	8.625	1018		WITH 600 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/13/2017 9:00 AM  
 Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
 Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 4880' WITH 2 SX CMT. PLUG AT 1060' WITH 15 SX GEL & 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
 Date/Time Plugging Completed: 01/13/2017 11:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 4880' WITH 2 SX CMT. 1ST PLUG AT 1072' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 552' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 25 SX CMT. CMT TO SURFACE. PULLED TBG. TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5336	5354		
5316	5320		
5268	5354		
5152	5157		
4930	4936		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

INVOICED

Plugged through: TBG

JAN 24 2017

District: 01

RECEIVED  
 JAN 20 2017  
 KCC DODGE CITY *MD*

Signed *Larry Harris* ECRS  
 (TECHNICIAN)  
*JA*