

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-20757-00-01  
Spot: NENWNE Sec/Twnshp/Rgc: 21-21S-11W  
330 feet from N Section Line, 1650 feet from E Section Line  
Lease Name: SMITH ESTATE B Well #: 2-21  
County: STAFFORD Total Vertical Depth: 3400 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3080		WITH 2 SX CMT
CIBP		3328		
PROD	4.5	3392	0	WITH 190 SX CMT
SURF	8.625	291		WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/13/2016 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 3080' WITH 2 SX CMT. TEST CASING TO 400#. PERFORATE AT 600' WITH 50 SX CMT (200# HULLS IN LAST 25 SX) PERFORATE AT 320' WITH CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/13/2016 1:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

12/13/16: SET CIBP @ 3080' WITH 2 SX CMT ON TOP. PRESSURE TEST 4 1/2" CASING TO 400 PSI. PERFORATE AT 600' & 320'. RAN TBG IN HOLE TO 600'. BREAK CIRCULATION WITH FRESH WATER. PUMP 50 SX CMT WITH 200# HULLS IN LAST 25 SX CMT MIXED. POOH WITH TBG TO 320' & PUMP 75 SX CMT TO SURFACE. PULL REMAINING TBG FROM HOLE. PUMP 55 SX CMT INTO 4 1/2" CASING & CIRCULATED UP 8 5/8" CASING TO SURFACE. TOP OFF CASING WITH 10 SX CMT. CASING & ANNULUS WAS CONFIRMED FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
3129	3284		

Remarks: USED 60/40 POZMIZ 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

INVOICED

JAN 24 2017

District: 01

RECEIVED  
JAN 11 2017  
KCC DODGE CITY

Signed

Ken Scofield  
5A  
(TECHNICIAN)