

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-147-30000-00-00  
Spot: SENESEW Sec/Twnshp/Rge: 35-4S-20W  
1650 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: STEPHENS Well #: 1  
County: PHILLIPS Total Vertical Depth: 3383 feet

Operator License No.: 5552 String Size Depth (ft) Pulled (ft) Comments  
Op Name: GORE OIL COMPANY PROD 4.5 3359 150 SX  
Address: 202 S ST FRANCIS PO BOX 2757 SURF 8.625 195 175 SX  
WICHITA, KS 67202

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/10/2017 11:00 AM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY DBA Phone: (785) 259-1928

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Production perforations: 3103' - 3236'.  
Packer and 6 joints tail pipe. Tubing pushed to bottom of hole.  
Casing leaks at 1994' - 2374'.  
Casing collapsed or parted at 3033'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/10/2017 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 900' and 1440'. Ran tubing to 2910' and pumped 100 sx cement w/200 # hulls.  
Pulled tubing to 1952' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 994' and  
pumped 35 sx cement w/100 # hulls. Circulated cement to surface. Pulled all tubing. Hooked  
to 4 1/2" casing and pumped 25 sx cement. Shut in pressure 150 psi. Hooked to 8 5/8" x 4 1/2"  
annulus and pressured to 150 psi immediately.

GPS: 39.65902 -099.54501

Perfs:

Top	Bot	Thru	Comments
3232	3236		
3121	3127		
3103	3109		

KCC WICHITA  
JAN 24 2017  
RECEIVED

Remarks: GLOBAL OILFIELD SERVICES TICKET # 2812

Plugged through: TBG

INVOICED

JAN 24 2017

District: 04

Signed

*Pat Bedore*

(TECHNICIAN)

CM

JAN 12 2016