



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 19 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Sharpe of Barnett Oil Co. has this date requested permission to plug the following described well:

Mr. Sharpe guarantees payment of the plugging fee.

Operator's full Name: Barnett Oil Co.

Complete Address: 411 First Nat'l Bldg. Wichita, Ks.

Lease Name: Wilson Well No. 7

Location: NE SW SW Sec. 21 Twp. 22 Rge. 15 (E)(W) XX

County: Paumee Total Depth 3090 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Sharpe was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace 70 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and displace 20 sc cement thru drill pipe. Heavy mud to 140' set cementing plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Leo F. Massey
 Conservation Division Agent