



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

15-155-02273-0000

May 8, 1963

5-20-63

RECEIVED  
 CONSERVATION COMMISSION  
 MAY 20 1963

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this

date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Frank J. Black

Complete Address: Box 150, McPherson, Kansas

Lease Name: Ira C. Johnson Well No. 3

Location: C NW SW Sec. 31 Twp. 23 Rge. 10 (W) X

County Reno Total Depth 3734' Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3710' and cement with 5 sacks.

Fill hole with mud to 260'. Set rock bridge from 260'

to 250' and cement with 20 sacks. Fill hole with mud

to 40'. Set rock bridge from 40' to 30' and cap hole

with 10 sacks cement.

Very truly yours,

*William J. Loman*  
 Conservation Division Agent