

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 25 1967

9-25-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Keevert of Birmingham-Bartlett has this

date requested permission to plug the following described well:

Mr. Keevert guarantees payment of the plugging fee.

Operator's full Name: Birmingham-Bartlett Drlg., CO.

Complete Address: 300 Kaufman Bldg., Wichita, Kansas

Lease Name: Dixon "A" Well No. 1

Location: 150' NW of NW NE Sec. 14 Twp. 22 Rge. 23 ~~(E)~~ (W)

County Hodgeman Total Depth 4579' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Keevert was instructed to plug the well as follows:

8 5/8" to 362' circulated w/ cement. T.D. 4579'

Mud 4579' to 1175' Spotted 100 sacks cement 1175' to 800'

Mud 800' to 355' Plug, & 25 sacks cement 355' to 265'

Mud 265' to 40' Plug, Hulls & 12 sacks cement 40' to 0'

Very truly yours,

Edmund J. Eves
Conservation Division Agent