

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1971
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mill Drilling Company, Inc.

Complete Address Box 349 Russell, Kansas 67665

Lease Name Shady Well No. A -1

Location NE NE NE Sec. 2 Twp. 22 Rge. (E) (W) 16

County Pawnee Total Depth 3928'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 9:45 A Day 15 Month 2 Year 1970

The above well was plugged as follows:

Total Depth 3928' 8 5/8 csg set at 830' cwc 400 sk.

5 1/2 csg set at 3918' cw 100 sk cmt.

5 1/2 csg PBTID 3860' with top perf. (3585')

Top of tubing at 1625'.

Set 5 1/2 plug at 1625' - poured 30 gal sd - dumped 5 sk cmt W/dump bailer. (1580-1625)

Recovered 1580' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/2 sk hulls, plug and 100 sk
poz 6%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Z. Massey
Well Plugging SupervisorDATE 2/18/71INV. NO. 3361-4