

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name John O. Farmer Inc
Complete Address: 370 W Wichita Russell, Kansas
Lease Name Snowberger Well No. 1
Location SE SE SW Sec. 29 Twp. 22 Rge. (E) (W) 16
County Pawnee Total Depth 4300
Abandoned Oil Well Gas Well x Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Forbes Casing Pulling
Address: Great Bend, Kans License No. 49
Operation Completed: Hour 12 Noon Day 18 Month 12 Year 63

The Above well was plugged as follows:

8 5/8" 254' circulated with cement - 5 1/2" 4257' with 100 sax cement - perforated 4113'

Set plug at 4100', sand and 4 sax cement - pulled 2650' 5 1/2" to 500', circulated hole with heavy mud through 5 1/2" (20 Sax Gel), displaced 25 sax cement through 5 1/2" at 500', heavy mud to 200', displaced ~~20~~ 25 sax cement through 5 1/2" at 200', heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Elden Letty*
Well Plugging Supervisor

DATE 12/23/63
INV. NO. 8318-W