

15-145-19021-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 8 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

2-8-71

Operator's Full Name Mull Drilling Company, Inc.

Complete Address Box 349 Russell, Kansas 67665

Lease Name Malin Well No. 2

Location NW NW NW Sec. 1 Twp. 22 Rge. (E) (W) 16

County Pawnee Total Depth 3953'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling, Inc.

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 3 P Day 6 Month 2 Year 1970

The above well was plugged as follows:

Total Depth 3953' 8 5/8 csg set at 961' cwc 500 sk.

5 1/2 csg set at 3953' cw 100 sk cmt.

5 1/2 csg PBTD 3903' with top perf. (3861')

Filled 5 1/2 csg W/sd (3800-3903) Dumped 5 sk cmt W/dump bailer. (3760-3800)

Cutoff and recovered 3200' of 5 1/2 csg.

Filled 8 5/8 csg W/mud to 375' - set 25' rock and gravel - dumped 5 yds readymix cmt to surface.

I hereby certify that the above Well was plugged as herein stated.

INVOICED

DATE 2/8/71
INV. NO. 3314-W

Signed: Leo J. Messing
Well Plugging Supervisor