

15-145-20647-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pawnee SEC. 1 TWP. 22S RGE. 16W E/W
Location as in quarters or footage from lines:
SE NE SW

Locate Well
correctly on above
Section Platt.

Lease Owner Halliburton Oil Producing Company
Lease Name W.T. Smith #1 Well No. _____
Office Address 2915 Classen Blvd. Okla City, Okla. 73106
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 3-15-83
Plugging completed 3-22-83
Reason for abandonment of well or producing formation _____

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom T.D. 3990'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	603'	none
				4-1/2"	3989'	2821'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped in 15 sacks gel and 25 sacks gel plus 25 sacks weight mud to kill salt water flow. Plugged off bottom with sand to 3875' and ran 4 sacks cement. Shot casing @3160', 2980', 2820' and pulled a total of 74 joints of 4-1/2" casing. Plugged well with 3 hulls, 20 gel, 1 hull, released plug and displaced with 250 sacks cement.
Plugging Complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 1983

My Commission expires: _____



Irene Hoover
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
3-24-83
MAR 24 1983
CONSERVATION DIVISION
Wichita, Kansas