

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

Form CP-4

15-009-19280-0000  
WELL PLUGGING RECORD

Barton County, Sec. 32 Twp. 16 Rge. 11 (W)

Location as "NE/CNW/SW" or footage from lines C SL NW NW  
Lease Owner National Cooperative Refinery Association  
Lease Name Joseph Dolechek Well No. 3  
Office Address Box 6, Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed June 12 1947  
Application for plugging filed May 8 1972  
Application for plugging approved May 9 1972  
Plugging commenced May 16 1972  
Plugging completed May 19 1972  
Reason for abandonment of well or producing formation Uneconomical

If a producing well is abandoned, date of last production April 1972  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan  
Producing formation Arbuckle Depth to top Bottom 3345' Total Depth of Well 3345 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	240'	8 5/8"		
		0	3342'	5 1/2"		1662.55'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand back 3345' to 3300'. Dump 5 sx. cement 3345' to 3310'. Pump  
3 sx. hulls and 20 sx. gel and 100 sx. cement @ 1000# pressure.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 1 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Ralph Comstock Pipe Pulling, Inc.  
Address 320 N. Park, Stafford, Kansas 67578

STATE OF KANSAS, COUNTY OF BARTON, ss.  
I, J. GOTSCHKE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Box 6, Great Bend, Kansas 67530  
(Address)

Subscribed and sworn to before me this 30th day of May 1972

My commission expires June 3, 1973  
Glenn E. Meier Notary Public.

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

COPY

Company - BLACK-MARSHALL OIL COMPANY  
Farm - Joseph (Dolechek) No. 3

SEC. 32 T. 16 R. 11W  
CS1 NW NW

Total Depth. 3345'

Comm. 6-4-47

Comp. 6-12-47


Shot or Treated.

Contractor. Black-Marshall Oil Co.

Issued. 8-30-47

County. Barton

KANSAS



CASING:  
8-5/8" 240' Cem. w/ 90 sx  
5-1/2" 3342' Cem. w/100 sx

Elevation. 1916

Production. 200 BO net, no wtr

Figures Indicate Bottom of Formations.

surface clay & sand	130
sand & shale	240
shale	290
sand	345
shale & red bed	765
anhydrite	835
shale & salt	1445
shale	1630
shale & shells	1795
lime brkn	1920
lime	1995
shale & lime	2120
shale & shells	2290
shale	2490
shale & shells	2625
shale & lime	2962
lime	3071
shale & lime	3200
lime	3288
shale & lime	3343
shale & lime	3345
Total Depth	

Tops:	
Anhydrite	765
Lansing K.C.	3071
Arbuckle	3341

RECEIVED  
STATE CORPORATION COMMISSION

MAY 9 - 1972

CONSERVATION DIVISION  
Wichita, Kansas