

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make, Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

15-009-03175-0000

Barton County. Sec. 32 Twp. 16S Rge. 11 (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW SE NW

Lease Owner National Cooperative Refinery Association

Lease Name JOSEPH Well No. 7

Office Address 305 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed June 15 1957

Application for plugging filed December 13 1960

Application for plugging approved December 15 1960

Plugging commenced December 26 1960

Plugging completed December 30 1960

Reason for abandonment of well or producing formation Depletion

If a producing well is abandoned, date of last production November 30 1960

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3357 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	309'	None
				5-1/2"	3355'	2405'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3357' and found it clear. Sanded hole from 3357' to 3345' and dumped 5' sacks of cement with dump bailer. Pulled 5 1/2" casing. Mudded hole to 300', set 10' rock bridge to 290' and ran 20 sacks of cement. Mudded hole to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 18 1961  
CONSERVATION DIVISION  
Wichita, Kansas  
01-18-61

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Company  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C.R. Sears (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) C.R. Sears (C.R. Sears)

305 Rule Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of January, 1961

My commission expires November 26, 1964 NELL McCOMB Notary Public.



WELL LOG

Date Started: 5-23-57  
Date Completed: 6-4-57

Joseph No. 7  
SW SE NW  
32-16-11  
Barton County, Kansas

8 5/8" set at 309'  
5 1/2" set at 3355' (2' off bottom)

Elevation	1912'	K.B.
Anhydrite	765'	(-1147)
Topeka	2673'	(-761)
Heebner	2963'	(-1051)
Leavenworth	2968'	(-1056)
Snyderville	2971'	(-1059)
Toronto	2981'	(-1069)
Douglas	2991'	(-1079)
Douglas Sand	3013'	(-1101)
Brown Lime	3060'	(-1148)
Lansing	3075'	(-1163)
Conglomerate	3337'	(-1425)
Gorham Sand	3346'	(-1434)
Arbuckle	3353'	(-1441)
R.T.D.	3357'	(-1445)

0' - 50'	Surface Clay and Rock
50' - 130'	Shale
130' - 160'	Sand
160' - 277'	Shale and Clay
277' - 298'	Sand
298' - 309'	Hard Shale
309' - 320'	Shale
320' - 335'	Dry Sand
335' - 340'	Shale and Sand
340' - 420'	Shale and Iron
420' - 765'	Red Bed
765' - 785'	Anhydrite
785' - 1240'	Shale and Shells
1240' - 1350'	Shale and Salt
1350' - 1740'	Shale and Shells
1740' - 1950'	Broken Lime
1950' - 2128'	Lime and Shale
2128' - 2650'	Lime and Shale
2650' - 2850'	Lime
2850' - 2963'	Lime
2963' - 3026'	Heebner
3026' - 3075'	Lime
3075' - 3130'	Lansing
3130' - 3226'	Lime
3226' - 3346'	Lime
3346' - 3353'	Gorham Sand
3353' - 3357'	Arbuckle
3357'	R.T.D.

REGISTERED  
STATE COMMISSION

DEC 14 1950

CONSERVATION DIVISION  
Wichita, Kansas

AFFIDAVIT

State of Kansas . . . . . County of Barton

I, Cecil M. Olson, employee of the owner, do swear that the statements and matter herein contained are true to the best of my knowledge.

THE DUKE DRILLING COMPANY

BY: Cecil Olson

Subscribed and sworn before me this 12th day of June, 1957.

Clair E. Stinson  
NOTARY PUBLIC

My commission expires: June 24, 1959.