

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

15-009-03174-0000
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County, Sec. 32 Twp. 16S Rge. 11 (E) W (W)

Location as "NE/CNW&SW&" or footage from lines NW NE NW

Lease Owner National Cooperative Refinery Association

Lease Name JOSEPH Well No. 6

Office Address 1417 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed August 8, 19 53

Application for plugging filed January 29, 19 65

Application for plugging approved February 1, 19 65

Plugging commenced February 18, 19 65

Plugging completed March 2, 19 65

Reason for abandonment of well or producing formation Depletion

If a producing well is abandoned, date of last production January 31, 19 65

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3340 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	296'	None
				5-1/2"	3335'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set Lane Wells plug at 2950 feet, dumped 1 sack of cement. Dumped 10 sacks of Salt Jel Mud, filled up to 200 feet from surface, set wood plug, dumped 20 sacks of cement on up to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1965 03-16-65

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor N. C. R. A. National Cooperative Refinery Association

Address 1417 Wichita Plaza, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

C. R. Sears (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)

1417 Wichita Plaza, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of March, 19 65

My commission expires February 28, 1967

Mary L. Lawrence
Mary L. Lawrence Notary Public.

WELL LOG
Joseph #6
NW NE NW of 32-16-11W
Barton County, Kansas

Started: July 14, 1953
Completed: July 27, 1953

RECEIVED
STATE CORPORATION COMMISSION

FEB 1 1955

CONSERVATION DIVISION
Wichita, Kansas

0-95	Surface clay and sand streaks
95-200	Blue shale and sand
200-248	Sand
248-340	Blue shale
340-750	Red bed and blue shale
750-783	Anhydrite
783-1345	Shale and shells
1345-1745	Shale, shells and lime streaks
1745-2025	Lime and shale
2025-2355	Lime and shale
2355-2670	Lime and shale
2670-2836	Lime
2836-2995	Lime
2995-3020	Cored-shale to 3003, sand good stain to 3012, shale to 3020
3020-3135	Lime
3135-3255	Lime
3255-3315	Lime
3315-3334	Lime
3334-3338	Arbuckle
3338	TOTAL ROTARY DEPTH

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton, SS

I, Lynn O. Duke, of the DUKE & WOOD DRILLING COMPANY being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Lynn O. Duke
Partner

Subscribed and sworn to before me this 9th day of September 1953.

Dean T. Cooley
Notary Public

My commission expires: April 29, 1957.