


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-009-03171-0000

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 32 Twp. 16 Rge. 11W (E) (W)
Location as "NE/CNW%SW%" or footage from lines SE SE SE
Lease Owner Bennett & Roberts Oil Operations
Lease Name Hitschman "C" Well No. 4
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 8/6 19 57
Application for plugging filed August 11 19 59
Application for plugging approved 8/12 19 59
Plugging commenced 8/19 19 59
Plugging completed 8/21 19 59
Reason for abandonment of well or producing formation Insufficient oil to
produce economically
If a producing well is abandoned, date of last production February 19 59
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman
Producing formation Arbuckle Depth to top 3323 Bottom _____ Total Depth of Well 3334 ^{PBTD} Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 344' | None |
| | | | | 3393' | 5 1/2" | 1707.57' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand to 3320, dump 5 sx cement. Mud to 320', set 10' rock bridge w/25 sx cement. Mud to 40', set 10' rock bridge w/10 sx cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

SEP 9 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 59

Clara Sumner
Notary Public.

My commission expires 6/17/62

PLUGGING
FILE SEC. 32 T. 16 R. 11W
BOOK PAGE 52 LINE 28

Bennett & Roberts Oil Operations
Hitchman C#4

SE SE SE Sec, 32-16-11
Barton County, Kansas

RTD 3393

CONTRACTOR: Bennett & Roberts Drilling Co.

Commenced 7/17/57
Completed 7/29/57

8 5/8" Set @ 344' w/150 sx. cmt.
5 1/2" Set @ 3393' w/100 sx cmt.

| | |
|------------------------|------|
| Surface Clay | 20 |
| Post Rock | 45 |
| Gray Shale | 325 |
| Blue Shale | 344 |
| Blue & Gray Shale | 734 |
| Anhydrite | 760 |
| Shale, Shells, Red Bed | 775 |
| Shale & Shells | 1360 |
| Shale & Shells | 1400 |
| Lime & Shale | 2150 |
| Shale & Lime streaks | 2390 |
| Shale & Lime | 2835 |
| Lime | 2930 |
| Lime & Shale | 3030 |
| Lime | 3393 |

RECEIVED
STATE CORPORATION COMMISSION

AUG 12 1957

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is true and correct
to the best of my knowledge.

BENNETT & ROBERTS DRILLING CO.

By John B. Turner

Subscribed and sworn to before me this 2nd day of August, 1957.

PLUGGING

FILE SEC. 32 T. 16 R. 11W

Clara Hummel
Notary Public

My Commission Expires 6/17/58 BOOK PAGE 59 LINE 28