


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-009-03170-0000  
**WELL PLUGGING RECORD**

Barton County, Sec. 32 Twp. 16 Rge. 11W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SE SE  
Lease Owner Bennett & Roberts Oil Operations  
Lease Name Hitschmann "C" Well No. 3  
Office Address Drawer 633, Russell, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 7/8 19 57  
Application for plugging filed 11/6 19 62  
Application for plugging approved 11/8 19 62  
Plugging commenced 11/8 19 62  
Plugging completed 11/16 19 62  
Reason for abandonment of well or producing formation No longer producing

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 10/10 19 62  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3320 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	301'	None
				5 1/2"	3319 1/2'	<del>18</del> 1766'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Check hole and made plug back with sand to 3300', mixed and ran 4 sacks cement through bailer. Mudded hole to 280' and set 10' rock bridge. Mixed and ran 1 sack calsea through dump bailer. Bailed hole down dry. Mixed and ran 25 sacks cement through dump biler. Mudded hole to 40' and set 10' rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

**RECEIVED**  
STATE CORPORATION COMMISSION

NOV 21 1962

11-21-62

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address Box 364, Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
Donald L. Roberts (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Russell, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November, 19 62

My commission expires 6/17/66

[Signature]  
Notary Public.



Bennett & Roberts Oil Operations  
Hitchman "C" #3

NE SE NE Section 32-16-11  
Barton County, Kansas

B.T.D. 3320\*

CONTRACTOR: Bennett & Roberts Drilling Co.

Commenced 6/26/57  
Completed 7/4/57

2 1/8" Set @ 301' w/150 oz. cut,  
3 1/8" Set @ 331 1/2' w/75 oz. cut,

Clay	35
Post Rock	45
Shale & Post Rock	80
Sand	95
Shal, Shells, Sandy Red Bed	283
Blue Shale	301
Blue & Grey Shale & Red Bed	570
Red Bed & Shale	735
Anhydrite	764
Shale & Shells	1190
Shale	1500
Shale & Linc	1750
Linc	1890
Linc & Shale	2815
Linc	2917
Linc & Shale	3045
Linc	3320

RECEIVED  
STATE CORPORATION COMMISSION  
MGV 8 1957  
CONSERVATION DIVISION  
Kansas

STATE OF KANSAS)  
BARTON COUNTY ) SS.

I hereby certify that the above information is true and correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING CO.

By John B. Thomas

Subscribed and sworn to before me this 10th day of July, 1957.

W. H. Thomas  
Notary Public

My Commission Expires 6/17/58