


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Russell County. Sec. 25 Twp. 14 Rge. 15 (E) (W) X  
Location as "NE/CNW/SW" or footage from lines CN2 SW SW  
Lease Owner Sierra Petroleum Co., Inc.  
Lease Name Harbaugh Well No. #3  
Office Address Box 232, Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved 12-13-63 19\_\_\_\_  
Plugging commenced 12-28-63 19\_\_\_\_  
Plugging completed 12-30-63 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3205' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Made plug back with sand to 3190', mixed and ran 5 sacks cement thru dump bailer.  
Mudded hole to 400' - sat 10' rock bridge. Mixed and ran 25 sacks cement thru  
dump bailer. Mudded hole to 40' - sat 10' rock bridge. Mixed and dumped 10  
sacks cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 2 1964

01-02-14  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer  
Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 31 day of December, 1963

My commission expires 24 October 1964  
Sidney D. Miller  
Notary Public.

Trans Era Petroleum, Inc.  
Harbaugh #3

C N/2 SW/4 SW/4 25-14-15  
Russell County, Kansas

Total Depth: 3205

Elev: 1767 GL

Comm: 4/17/56  
Comp: 4/25/56

Casing:

Cement

8 5/8 @ 320'  
5 1/2" @ 3204

375 sks cement 2% Gel 1 1/2 CC  
100 sks cement

FORMATION	DEPTH
Surface clay & shale	30
Shale & sand	95
Shale & shells	375
Sand	440
Red Bed	810
Anhydrite	850
Shale & red had	960
Shale	1220
Shale & salt	1250
Shale & shells	1500
Shale, lime & shells	1760
Lime & shale	2910
Lime	3102
Lime & shale	3195
Lime	3203
Corham Sand	3205

RECEIVED  
STATE CORPORATION COMMISSION

DEC 13 1963

CONSERVATION DIVISION  
Wichita, Kansas

Tops:	Anhydrite	810
	Harbner	2910
	Toronto	2929
	Douglas	2945
	Lansing K.C.	2969
	Corham Sand	3203

STATE OF KANSAS }  
COUNTY OF RUSSELL } 551

I hereby certify that the above information is true and correct  
to the best of my knowledge.

C. D. Honaker

Subscribed and sworn to before me this 27th day of April, 1956.

Margie Cooper  
Notary Public

My commission expires 1-30-57.