


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Call or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Hodgeman County. Sec. 14 Twp. 22S Rge. (E)23 (W)  
Location as "NE/CNW/SE/SW" or footage from lines 150' N of C SE NW  
Lease Owner PICKRELL DRILLING COMPANY  
Lease Name LEE "B" Well No. 1  
Office Address 705 4th Natl Bank Bldg, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 17, 19 63  
Application for plugging filed April 17, 19 63  
Application for plugging approved April 17, 19 63  
Plugging commenced April 17, 19 63  
Plugging completed April 17, 19 63  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4705 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	274'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 250'. Set plug. Cemented with  
20 sacks cement. Heavy mud to 40'. Set plug.  
Cemented with 15 sacks cement to bottom of  
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

APR 25 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PICKRELL DRILLING COMPANY  
Address 705 4th National Bank Bldg, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

(Signature of owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) C. W. Sebitt  
705 4th Nat'l Bk Bldg, Wichita 2, Kansas  
(Address)

Subscribed and sworn to before me this 22nd day of April, 1963

My commission expires

June 21, 1966

Maxine Blackman  
Notary Public.



**ROTARY DRILLING LOG**

COMPANY: PICKRELL DRILLING COMPANY  
705 4th National Bank Bldg, Wichita, Ks.

Rotary Drilling Commenced 4---3-63

Rotary Drilling Completed 4--16-63

LOCATION: Lee "B" No. 1 - 150' N of C SE NW  
Sec. 14-22S-23W, Hodgeman, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: (7 jts) 8 5/8" Surface Casing set at 274', cemented with 185 sacks cement. Circulated. Completed 4:30 P.M. No oil string run, D & A.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

60	Top Soil - Post Rock	C. F. S.
274	Shale & Shells	4573
395	Shale	4580
475	Sand	4590
990	Red Bed & Shale	4595
1220	Sand	4599
1280	Red Beds & Shale	4705
1535	Shale & Shells	
1570	Anhydrite	
1900	Shale & Shells	Slope Tests
2230	Shale, Lime & Shells	3000
2390	Lime & Shale	3500
3005	Lime	4000
3165	Lime & Shale, Sandy	4500
3380	Lime & Shale	
3480	Lime & Shale, Sandy	
4455	Lime	S. L. M.
4480	Lime & Shale	3512
4520	Ft. Scott Lime	4150
4550	Lime	4585
4560	Lime & Shale	
4685	Mississippian	
4705	Gilmore City Lime & TD	

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 25 1963

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 22nd day of April, 1963, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman  
Maxine Blackman Notary Public

