


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 5 Twp. 22 Rge. 16W (X) (W)
Location as "NE/CNW%SW%" or footage from lines CE/2 NE NE
Lease Owner Rocket Drilling Company, Inc.
Lease Name Parrish Well No. 1
Office Address 352 North Broadway, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed 6-13-1956 19__
Application for plugging filed December 9, 1958 19__
Application for plugging approved December 9, 1958 19__
Plugging commenced December 9, 1958 19__
Plugging completed December 12, 1958 19__
Reason for abandonment of well or producing formation no longer commercially
productive
If a producing well is abandoned, date of last production November 19 58
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Arbuckle Depth to top _____ Bottom _____ Total Depth of Well 3884 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	980'	0'
				5 1/2	3884'	3107.18

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Sanded back to 3825, mixed and dumped 5 sacks cement
Squeezed hole with 20 sacks fill and 100 sacks cement, filling surface
pipe from 300' to base of cellar with cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rocket Drilling Company, Inc.
Address 352 North Broadway, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. H. Myrick (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. H. Myrick
352 North Broadway, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of February, 19 59

My commission expires 8-7-1961 Zeeva Ford Notary Public.

PLUGGING
FILE SEC. S. T. 22 R. 16W
BOOK PAGE 3 LINE 2



Rocket Drilling Company, Inc.
 #1 Parrish Unit
 C E/2 NE/4 NE/4 Section 5-22S-16W
 Pawnee County, Kansas

Elevation: 1995 Gr.; 1998 D.F.; 2000 R.B.
 Spudded: June 4, 1956
 Rotary Completed: June 13, 1956
 Contractor: Rocket Drilling Company, Inc.

CASING RECORD

980' 8-5/8" O.D. 24# seamless casing cemented with 410 sacks cement.
 3884' 5-1/2" O.D. 14# seamless casing cemented with 110 sacks cement.

DRILLERS LOG

Sand & Clay	0	to	105	Lime	2130
Clay & Shale			315	Sand	2140
Sand			350	Lime	2185
Shale			415	Sand	2200
Sand			525	Lime	2305
Shale			565	Lime & Shale	2435
Sand & Shale			625	Shale	2790
Shale			974	Shale & Lime	2930
Anhydrite			1010	Lime	3310
Shale & Shells			1400	Lime & Shale	3536
Shale & Salt & Lime			1910	Lime	3830
Shale & Lime			2020	Shale	3840
Lime			2030	Arbuckle	3884
Sand			2045		

RECEIVED
 STATE CORPORATION COMMISSION

DEC 10 1958

CONSERVATION DIVISION
 Wichita, K. 67202

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby certify that to the best of my knowledge and belief the foregoing log is true and correct.

ROCKET DRILLING COMPANY, INC.

James W. Thompson
 James W. Thompson

Subscribed and sworn to before me, a Notary Public, in and for the County and State aforesaid, this 18th day of June, 1956.

My commission expires:
 10/28/1959

James Helmer Jence
 Notary Public

PLUGGING
 FILE SEC. 5 T. 22 R. 16W
 BOOK PAGE 3 LINE 2