

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County. Sec. 5 Twp. 22 Rge. 16 (E) 16 (W)

Location as "NE/CNW&SW&" or footage from lines C S/2 SW/4 NE/4

Lease Owner Rocket Drilling Company, Inc.

Lease Name CITY OF LARNED Well No. 1

Office Address 204 Derby Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed December 10, 1956

Application for plugging filed verbally - December 9, 1956

Application for plugging approved verbally - December 9, 1956

Plugging commenced December 10, 1956

Plugging completed December 10, 1956

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3883 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	993'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Set 1 plug at 300' with 100 sacks cement.
Filled to top.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation

Address 801 Union Center, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
I, Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling

801 Union Center, Wichita, Kansas.

(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of December, 1956

Dean R. Petty
STATE CORPORATION COMMISSION

Notary Public.

My commission expires June 16, 1959

PLUGGING
FILE SEC 5 T. 22 R. 16 W
BOOK PAGE 124 LINE 34

JAN 8 1957 1-8-57
CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

COMPANY: Rocket Drilling Company, Inc.
 CONTRACTOR: Musgrove Petroleum Corporation
 PAPER: CITY OF LARRED #1
 LOCATION: C E/2 SW/4 NE/4
 Sec. 5-22-16, Pawnee County, Ks.
 COMMENCED: November 30, 1956
 COMPLETED: December 10, 1956

0	90	Sand & surface soil
90	385	Clay, shale & sand
385	425	Shale
425	565	Sand
565	726	Shale & red bed
726	930	Red bed & shells
930	979	Shale & iron
979	983	Shale
983	1010	Anhydrite
1010	1580	Shale & shells
1580	1890	Shale & lime streaks
1890	2625	Shale & lime
2625	2800	Shale & lime streaks
2800	3304	Shale & lime
3304	3365	Lime
3365	3465	Shale & lime
3465	3675	Lime
3675	3866	Lime & shale
3866	3883	Lime
	3883	Rotary Total Depth

Set 8-5/8" surface pipe at 993' with 425 cc cement, 1% calcium chloride.

DRY AND ABANDONED

ELEVATION:	2004' K. H.		
TOBS:	Hechler 3408' (-1404)	Conglomerate	9830' (-1826)
	Er. In. 3509' (-1505)	Eros. Artuckle	9868' (-1824)
	Leasing 3519' (-1515)	R. B. T. D.	3883'

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK)

I, GORDON L. KOLLIER, do hereby certify that the above and foregoing is a true and correct copy of the log of the CITY OF LARRED #1, C E/2 SW/4 NE/4, Section 5-22-16W, Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY *Gordon L. Kollier*
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 12th day of December, 1956.

Leah Joyce Hefce
 Notary Public

My commission expires June 16, 1959

PLUGGING
 W 57 22 R 16W
 POOR PAGE 124 LINE 34

NOTARY PUBLIC
 1957
 GORDON L. KOLLIER