

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County, Sec. 5 Twp. 22S Rge. 16W (E) (W)

Location as "NE/CNW4SW4" or footage from lines SE SE SE

Lease Owner A. F. Brann

Lease Name Bahls Well No. 1

Office Address 513 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed March 6 19 56

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced April 1 19 57

Plugging completed April 6 19 57

Reason for abandonment of well or producing formation Making too little oil to operate

If a producing well is abandoned, date of last production February 13 19 57

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Brundage

Producing formation Arbuckle Depth to top Bottom Total Depth of Well 3907 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|---|--------|------------|
| | | | | 8-5/8" | 990' | None |
| | | | | 5-1/2" | 3904' | 2450' |
| | | | | Hole was plugged back to 3874' and casing perforated from 3851' to 3855'. | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled the hole with sand from 3874' to 3840' and ran 5 sacks of cement. Mudded the hole to 350', set a 10' rock bridge and ran 20 sacks of cement to 270'. Mudded the hole to 25', set a rock bridge to 17' and ran 5 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. A. F. Brann (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *A. F. Brann*

513 Union Center, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of April, 19 57

My commission expires May 18, 1959

Douglas R. Brann
Notary Public.

PLUGGING
FILE SEC 5 T. 22 R. 16W
BOOK PAGE 146 LINE 31

APR 17 1957 4-17-57
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

Company: A. F. BRAUN

Sec. 5 Twp. 22S Rge. 16W
Location: SE SE SE
Pawnee County, Kansas

Farm: BAHL'S No. 1

Total Depth: 3907
Commenced: 2-24-56
Completed: 3-6-56
Contractor: GREENLAND DRILLING COMPANY

Casings: 8-5/8" 990'
5-1/2" 3907'
Elevation: 2008 MB
Production:

Figures Indicate Bottom of Formations

| | | | |
|------|-------------------------|--------------|------|
| 125 | Sand and soil | TOPS: | |
| 430 | Shale and shells | Dakota Sand | 430 |
| 520 | Sand | Anhydrite | 584 |
| 560 | Red bed and sand | Rebner | 3100 |
| 775 | Red bed and shale | Brown lime | 3510 |
| 984 | Shale and shells | Lansing | 3516 |
| 1012 | Anhydrite | Base K.O. | 3740 |
| 1100 | Shale and shells | Conglomerate | 3810 |
| 1550 | Shale and shells w/salt | Simpson | 3816 |
| 1815 | Shale and shells | Arbuckle | 3852 |
| 2120 | Lime and shale | T.D. | 3907 |
| 2165 | Lime | | |
| 2415 | Lime and shale | | |
| 2690 | Shale and lime | | |
| 2980 | Lime and shale | | |
| 3160 | Lime and shale and silt | | |
| 3311 | Lime and shale | | |
| 3368 | Silt, lime and shale | | |
| 3395 | Lime and shale | | |
| 3467 | Lime | | |
| 3509 | Shale and sandy shale | | |
| 3512 | Brn. lime | | |
| 3516 | Shale and lime | | |
| 3535 | Lans. lime | | |
| 3740 | Lime | | |
| 3810 | Lime and shale | | |
| 3818 | Conglomerate | | |
| 3856 | Simp. shale | | |
| 3907 | Lime | | |

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:

I, Richard S. Davis, of the Greenland Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Bahls well.

Richard S. Davis
Richard S. Davis, Vice-President

Subscribed and sworn to before me this 9th day of March, 1956.

My commission expires March 15, 1960.

Verdina B. Rutledge
Verdina B. Rutledge, Notary Public

PLUGGING
FILE SEC. 5 T. 22 R. 16W
BOOK PAGE 146 LINE 31

RECEIVED
STATE COMMISSION
APR 17 1957
CONSERVATION DIVISION
Wichita, Kansas