

Give All Information Completely
Make Required Affidavit
Mail or Deliver to
Conservation Division
State Corporation Commission
314 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 2 Twp. 22 Rge. 16 (E) (W)

Location as "NE/CNWSW" or footage from lines. NE NE NE
Lesse Owner Mull Drilling Company, Inc.

Lease Name Shady Well No. A-1

Office Address P. O. Box 349 Russell, Kansas 67665

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 10

Application for plugging filed 12-21-70 10

Application for plugging approved 12-22-70 10

Plugging commenced 1-13-71 10

Plugging completed 2-15-71 10

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 10

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 3928 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 830 | None |
| | | | | 5 1/2 | 3918 | 1585' .54 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed a plug to 1625'; dumped 20 gallons of sand, and 5 sacks of cement. Shot casing at 1580' and laid down 51 joints. Squeezed well with 2 sacks of hulls, 20 sacks of gel and 100 sacks of 50/50 pozmix cement with 6% gel added.

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well to be filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold

P. O. Box 221 Great Bend, Kansas

(Address)

Subscribed and sworn to before me this 21 day of February, 1971



(Signature) [Notary Signature]

Notary Public.

My commission expires May 27, 1973

DRILLING RECORD

Well #1 Shady "A"
 Located NE NE NE Sec. 2-22-16W
 Pawnee County, Kansas

Casing Record

833' of 8-5/8" OD surface pipe
 cemented with 400 sacks

 3918' of 5 1/2" OD Casing
 cemented with 100 sacks

Work Commenced 1/20/52
 Drilling commenced 1/21/52
 Drilling completed 2/4/52

WELL LOG

| | |
|----------------------|-----------------|
| Sand | 0 to 110 |
| Clay, Shale & Shells | 110 to 200 |
| Blue Shale | 200 to 410 |
| Sand | 410 to 500 |
| Red Bed | 500 to 960 |
| Anhydrite | 960 to 990 |
| Lime & Shale | 990 to 1200 |
| Shale & Salt | 1200 to 1400 |
| Shale | 1400 to 1470 |
| Shale & Shells | 1470 to 1700 |
| Shale & Lime | 1700 to 2025 |
| Lime | 2025 to 2140 |
| Lime & Shale | 2140 to 2595 |
| Shale & Shells | 2595 to 2725 |
| Shale | 2725 to 2875 |
| Shale & Shells | 2875 to 2965 |
| Shale & Lime | 2965 to 3050 |
| Sandy Lime & Shale | 3050 to 3130 |
| Shale & Lime | 3130 to 3220 |
| Lime | 3220 to 3265 |
| Lime & Shale | 3265 to 3335 |
| Lime | 3335 to 3394 |
| Shale & Lime | 3394 to 3493 |
| Lime | 3493 to 3584 |
| Cherty Lime | 3584 to 3614 |
| Lime | 3614 to 3852 |
| Shale | 3852 to 3862 |
| Sand | 3862 to 3879 |
| Shale & Lime | 3879 to 3912 |
| Sand | 3912 to 3916 |
| Lime | 3916 to 3921 TD |

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 23 1970
 CONSERVATION DIVISION
 Wichita, Kansas