


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15-145-01099-0000

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Paynee \_\_\_\_\_ County. Sec. 29 Twp. 22 Rge. 16W (E) \_\_\_\_\_ (W)  
Location as "NE/CNW/SW" or footage from lines SW SE  
Lease Owner John O. Farmer, Inc.  
Lease Name Snowberger Well No. # 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 5-19-61 19\_\_\_\_  
Application for plugging approved yes 19\_\_\_\_  
Plugging commenced 5-23-61 19\_\_\_\_  
Plugging completed 6-3-61 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4175' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>1 1/2"</u>		<u>2,089'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugging commenced 5-23-61. Plugging completed 6-3-61.

Measured in to total depth: 4175'.

Plugged off bottom: Sanded back to 3925' and dumped 4 sacks of cement.

Worked & shot casing. Loaded hole with water. Spotted oil. Worked casing. Spotted 40 barrels of oil, after circulating 20 sacks of mud and 1 sack of hulls. Worked & shot casing. Worked and shot 1 1/2" casing free at 2,089'. Built rack and slide. Pulled and layed down casing.

Plugged well: Mudded hole up to 300' and set 10' rock bridge at 300'. Dumped 20 sacks of cement. Mudded hole up to 40' and set 10' rock bridge at 40'. Capped the well with 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

JUN 19 1961 6-19-61

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of June, 1961

My commission expires December 8th, 1963

Kayann Jenkins  
Kayann Jenkins  
Notary Public.

