


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 23 Twp. 22S Rge. (E) 15 (W)
Location as "NE/CNW/SW" or footage from lines NE SE NW
Lease Owner O. A. Sutton
Lease Name Lewis Well No. 1
Office Address 800 Sutton Place, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 18 1973
Application for plugging filed August 18 1973
Application for plugging approved August 18 1973
Plugging commenced August 18 1973
Plugging completed August 18 1973
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Traut
Producing formation Depth to top Bottom Total Depth of Well 4030 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	268'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Plug at 600' with 50 sacks cement; plug at 240' with 25 sacks cement; plug at 40' and bridge to hold Kelly - 10 sacks cement. Job complete at 2:30 p.m. 8-18-73.

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones, Inc.
Address 800 Sutton Place, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Jack G. Paulsen (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack G. Paulsen
Jack G. Paulsen
800 Sutton Place, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of August, 1973.
Jean S. Taylor Notary Public
My commission expires June 28, 1974.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1973

LEWIS #1
NE SE NW
Section 23-22S-15W
Pawnee County, Kansas


CONSERVATION DIVISION
Wichita, Kansas

Commenced: August 8, 1973
Completed: August 18, 1973

OPERATOR: O. A. SUTTON

Depth From	To	Formation	Remarks
0	80	Sand-surface clay	Ran 7 jts of used 28# 8 5/8" csg.
80	275	Shale	set @ 268' cemented w/225 sks
275	395	Shale-shells	common, 3% CC, 2% Gel
395	460	Sand	Cement Circ.
460	925	Shale	P.D. @ 8:30 PM 8/8/1973
925	952	Anhydrite	
952	1240	Shale	
1240	1525	Shale-salt	
1525	1715	Shale-lime	
1715	2185	Lime-shale	
2185	2335	Lime	
2335	2645	Lime-shale	
2645	3024	Shale-lime	
3024	3120	Lime-shale	
3120	3265	Shale-lime	
3265	3380	Lime	
3380	3470	Lime-shale	
3470	3560	Shale-lime	
3560	3820	Lime	
3820	3860	Lime-shale	
3860	3880	Conglomerate	
3880	3930	Lime-cherty	
3930	4030	Lime	
4030	TD		DRY AND ABANDONED

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the NE SE NW, Section 23-22S-15W, Pawnee County, Kansas, to the best of my knowledge and belief.


James S. Sutton, II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 23rd day of August, 1973, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the 24 day and year last above written.


Marjorie Hall, Notary Public

