

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County. Sec. 21 Twp. 22S Rge. 15W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE SW SW

Lease Owner Barnett Oil Company
Lease Name Wilson-Hendricks Well No. 1
Office Address 411 1st Natl. Bank Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 17 19 68
Application for plugging filed September 17 19 68
Application for plugging approved September 17 19 68
Plugging commenced September 17 19 68
Plugging completed September 17 19 68
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Box 582, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3990 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing		0	248'	8 5/8"	248'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug:
540'/70 sacks cement
240'/20 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1968
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Hellar Drilling Company, Inc.
Address 3394 Union Center, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
D. L. Hellar, Pres. of Hellar Drlg. Co. Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar D. L. Hellar, President
339 Union Center, Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 19th day of September, 19 68

My commission expires March 25, 1972
Catherine Darcey - Notary Public.



DRILLER'S LOG

COMPANY: Barnett Oil Company, Wichita, Kansas
 CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas
 LEASE: #1 Wilson-Hendricks
 LOCATION: NE SW SW 21-22S-15W, Pawnee County, Kansas
 COMMENCED: September 9, 1968
 COMPLETED: September 16, 1968
 CASING: Set 8 5/8" Surface Casing @ 248'/200 sacks cement

0-175	Shale & Sand
175-249	Shale
249-500	Sand & Shale
500-952	Shale & Red Beds
952-974	Anhydrite
974-1485	Shale & Red Beds
1485-1870	Salt Section
1870-2270	Ft. Riley lime & chert
2270-3530	Lime & Shale
3530-3640	Lsg. K. C. Lime
3640-3737	K. C. lime
3737-3944	Lime & Shale
3944-3973	Simpson shale & sand
3973-3990	Arbuckle dolomite
3990	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 23 1968
 CONSERVATION DIVISION
 Wichita, Kansas

D & A

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Wilson-Hendricks, located in NE SW SW 21-22S-15W, Pawnee County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 19th day of September, 1968.

Catherine Darcey
 Notary Public - Catherine Darcey



My Commission Expires: March 25, 1972.