


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Pawnee County, Sec. 21 Twp. 22 Rge. 15W (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNWSW" or footage from lines _____
Lease Owner Santa-Fe Pipe & Supply Company
Lease Name Wick Well No. #1
Office Address Box 407, Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced 5-12 1959
Plugging completed 5-17 1959
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3980' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	Surface	
				5 1/2"		3,533'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 3980'.
Plugging started 5-12-59. Finished 5-17-59.
Plugged off bottom and sanded from 3980' to 3960'. Dumped 5 sacks of cement. Worked and shot pipe. Shot 5 1/2" casing at 3,533'. Pumped in 20 sacks of mud and 19 bbls water. Finished pulling pipe. Pumped plug to 253', using 75 sacks of cement. Well completed.

5-26-59
REC'D
STATE CORP. COMMISSION
MAY 26 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of May, 1959

Betty S. Edman
Notary Public.

My commission expires November 8, 1960.

PLUGG G.
FILE SEC. 21 T. 22 R. 15E
BOOK PAGE 58 LINE 14

D. F. O'ROURKE

SW SE SW Sec. 21-22S-15W
Pawnee County Kansas

Wick No. 1

Commenced: Jan. 1, 1958
Completed: Jan. 9, 1958

Casing Records: 248' 3 5/8" cen. with 200 sacks - 2 sack Calcium Chloride
3973' 5 7/8" cen. with 100 sacks

Elevation: GM 2000; BP 2008; TD 2005

17 BOPD

Drillers Log

Clay and shale	170
shale	270
red bed	410
Dakota sand	495
Red Bed	960
Anhydrite	1000
shale & shells	1200
salt & shells	1350
shale & shells	1625
lime & shale	2060
lime	2225
shale & lime	2740
shale & broken lime	2900
lime & shale	3160
lime (broken)	3250
lime	3480
Douglas shale	3480
lime	3842
Conglomerate	3858
Viola chert	3985
lime	3980
lime & shale	3982
shale, sand & lime	3976
lime	3980 RFD

Topo Sink
Heel 3410
Line 3540
Core 3840
Well 3855
Depth 3971

Wichita, Kansas
January 20, 1958

I hereby certify that the above is a true and correct log of the Wick No. 1 well, to the best of my knowledge and belief.

John R. Knightley

John R. Knightley

Subscribed and sworn to before me this 20th day of January, 1958.

Notary Public

Notary Public

My commission expires Sept. 14, 1958.

RECEIVED
STATE CORPORATION COMMISSION

MAY 26 1958

CONSERVATION DIVISION
WIC

PLUGGING
FILE SEC. 21 T. 22 R. 15W
BOOK PAGE 38 LINE 14