


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County. Sec. 28 Twp. 22S Rge. 15W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C-NW SW

Lease Owner Lowry's Lease Management
Lease Name Lovett Well No. 1
Office Address Box 1578, Liberal, Kansas 67901
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed December 5, 1980
Application for plugging filed Verbal Application 1980
Application for plugging approved Verbal Approval 1980
Plugging commenced December 5, 1980
Plugging completed December 5, 1980
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 1980

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 4,046'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 975' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 4,046 ft. (rotary total depth) to 920 ft. Set plug at 920 ft. and cemented with 60 sacks cement. Filled hole with heavy rotary mud from 920 ft. to 270 ft. Set plug at 270 ft. and cemented with 30 sacks cement. Filled hole with heavy rotary mud from 270 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole and 5 sacks cement in mouse hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Box 169, Great Bend, Kansas 67530.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent ~~xxxxxx~~ of owner) ~~xxxxxx~~


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Dean Britting
251 N. Water-Suite 10, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of December, 19 80

My commission expires July 25, 1982

Elsie Willison
Elsie Willison - Notary Public.



1-6-81

KANSAS DRILLERS LOG

COMPANY Lowry's Lease Management

SEC. 28 T.22S R. 15W

FARM Lovett NO. 1

LOC. C-NW SW

COUNTY Pawnee

ROTARY TOTAL DEPTH 4,046'

COMM. November 24, 1980 COMP. December 5, 1980

CONTRACTOR FREEMAN DRILLING COMPANY (Rig #1)

ISSUED December 19, 1980

CASING

10 3/4"

8 5/8" Set at 975' cemented w/550 sxs cement

ELEVATION 2,015' K.B.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

| | |
|--------------------|--------|
| Sand and Shale | 280' |
| Shale | 420' |
| Sand | 465' |
| Sand and Shale | 720' |
| Red Bed and Sand | 964' |
| Anhydrite | 976' |
| Shale | 1,926' |
| Shale and Lime | 2,200' |
| Lime and Shale | 2,940' |
| Chert and Lime | 2,957' |
| Lime and Shale | 4,036' |
| Lime and Chert | 4,046' |
| Rotary Total Depth | 4,046' |

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas)
) ss:
County of Sedgwick)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 19th day of December, 1980.

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982

STATE RECEIVED
JAN 6 1981
CONSERVATION DIVISION
Wichita, Kansas