

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-145-20,554-0000

LEASE NAME Bowman

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER B-1

 Ft. from S Section Line

 Ft. from E Section Line

C E $\frac{1}{2}$ E $\frac{1}{2}$ SE $\frac{1}{4}$
 SEC. 31 TWP. 22S RGE. 15 (R) or (W)

LEASE OPERATOR GOULD OIL, INC.

ADDRESS 110 NORTH MARKET #411 WICHITA, KS. 67202

PHONE# (316) 265-5523 OPERATORS LICENSE NO. 5298

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

COUNTY PAWNEE

Date Well Completed

Plugging Commenced October 3, 1990

Plugging Completed October 9, 1990

The plugging proposal was approved on October 4, 1990 (date)

by Duane Rankin was on location for the top hole plug. (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3800

Show depth and thickness of all water, oil and gas formations. PBID: 3029 Perfs: 2864-2870

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	346	8 5/8	346	0
			3029	4 1/2	3029	2421'
Also recovered .33 jts. of 2 3/8 upset tubing and 62 jts. of 2 3/8 regular tubing.						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set

Oct. 3, 1990: Moved in, pulled tubing, dumped sand to 50' above top perfs, and dumped 4 sx. cement. Bond log top of cement was 2466'.

Oct. 4, 1990: Dia log found free point and shot off casing at 2421'. Pulled and recovered same. Oct. 9, 1990: Top hole plug: 300# hulls, 10 gel, 50 sx cement, 10 gel.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address North highway 61 Pratt, Kansas 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GOULD OIL, INC.

STATE OF Kansas COUNTY OF Pratt, ss.


Judy Berry OF PLUGGING CONTRACTOR

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts: statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Judy Berry

10-19-90

OCT 19 1990 (Address) Pratt, Kansas



SUBSCRIBED AND SWORN TO before me this 17th day of October, 1990

Dorothy M. Ferguson Notary Public

My Commission Expires Feb. 6, 1993

150# hulls, 150 sx. cement. All 60-40-pox, 6% gel. On Oct. 10, found top of cement at 150' down from top. Dumped redi mix to top. Approved by Steve Durant at Dodge City office.