

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee

County. Sec. 24 Twp. 22S Rge. (E) 15 (W)

Location as "NE/CNW&SW&" or footage from lines C NW NE SE

Lease Owner SUNRAY MID-CONTINENT OIL COMPANY

Lease Name Barstow Well No. 1

Office Address Box 788, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 12 19 57

Application for plugging filed November 12 19 57

Application for plugging approved November 13 19 57

Plugging commenced November 12 19 57

Plugging completed November 12 19 57

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4043 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	490'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud to 470'. Set plug, 1/2 sack hulls and 25 sacks cement.
Filled with heavy drilling mud to 40', set plug, 1 sack hulls and cement to surface.

Well log attached.

RECEIVED
STATE CORPORATION COMMISSION
NOV 23 1957
CONSERVATION DIVISION
WICHITA, KANSAS

11-23-57

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

N. E. Montgomery (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) N. E. Montgomery

Box 788, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of November, 19 57

Not Public

Notary Public.

My commission expires December 21, 1960

PLUGGING
NOV 24 1957
BOOK PAGE 60 LINE 84

Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
November 19, 1957

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: November 1, 1957
Drilling Completed: November 12, 1957

H. F. Barstow #1 SE/4
Sec. 24-22S-15W, Pawnee
County, Kansas.

DRILLERS LOG

Depth Figures indicate base of formation:

Surface	0
Sand	160
Shale & Shells	350
Dakota Sand	450
Red Bed Shale	475
Red Bed	491
Red Bed Shale	912
Anhydrite	936
Red Bed & Shale Shells	1150
Shale & Shells	1900
Shale & Lime	1950
Lime	2095
Lime With Shale Streaks	2255
Lime Shale	2395
Shale	2555
Shale & Lime	2740
Lime & Shale	2885
Shale & Lime	2995
Lime & Shale	3543
Lansing Lime	3575
Lime	3635
Lime & Shale	3680
Lime	3745
Lime & Shale	3830
Lime	3882
Cherty Lime	3958
Sandy Shale & Lime	4018
Arbuckle Lime	4030
Lime	4043 TD

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's H. F. Barstow #1 SE/4 Section 24-22S-15W, Pawnee County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1960
My Commission Expires

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1957

PLUGGING
SEC. 24 T. 22 R. 15W
BOOK PAGE 60 LINE 44