


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 24 Twp. 22 Rge. 15 (W) (W)
Location as "NE/CNW/SW" or footage from lines NE SW SW
Lease Owner Petroleum, Inc.
Lease Name ACKERMAN Well No. 1
Office Address 305 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 5, 19 54
Application for plugging filed March 5, 19 54
Application for plugging approved March 5, 19 54
Plugging commenced March 5, 19 54
Plugging completed March 5, 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1060 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	230'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up to 220'. Push wooden plug
to 225'. Cemented and displaced
20 sacks cement through drill pipe
on to plug at 225'. Mudded up to
40' and set second wooden plug at
40'. Filled hole to bottom of well
cellar with 10 sacks cement.

3-11-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. W. Fisher (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. W. Fisher*

305 East Third, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 19 54

Sharon Friedman
Notary Public.

My commission expires October 13, 1954.

24-7388-5 3-53-20M
PLUGGING
FILE SEC 24 T 22 R 15 W
PAGE 18 LINE 6

WELL LOG

COMPANY **Petroleum, Inc.**

SEC. **24** T. **22** R. **15**

FARM **ACKERMAN**

NO. **1**

LOC. **NE SW SW**


TOTAL DEPTH **4060'**

COUNTY **Parsons County, Ks.**

COMM. **February 22, 1954.**

COMP. **March 5, 1954.**

CONTRACTOR **Garvey Drilling Co.**



CASING **8-5/8" @ 230' w/200 cas.**

ELEVATION **1981' A.B.**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Tops

130 Sand & Shells
 370 Shale & Shells
 445 Sand
 920 Shale & Red Bed
 940 Anhydrite
 1810 Shale & Shells
 2035 Lime
 2210 Shale & Lime
 2310 Lime
 3065 Lime & Shale
 3259 Lime
 3352 Lime & Shale
 3890 Lime
 3937 Cherty Lime & Shale
 3961 Cherty Lime
 4002 Lime & Sandstone
 4020 Lime & Shale
 4033 Conglomerate
 4047 Sand & Lime
 4060 Lime
 4060 R.T.D.

Heebners: 3417 (-1436)
 Brown Limes: 3540 (-1559)
 Lansings: 3551 (-1570)
 Base of
 Kansas City: 3784 (-1803)
 Viola: 3885 (-1904)
 Cherty Viola: 3909 (-1928)
 Simpson: 3975 (-1994)
 Arbuckles: 4035 (-2054)

NOTARIAL PUBLIC
 COUNTY OF PARSONS, MISSOURI
 My Commission Expires

PLUGGING
 FILE SEC 24 T 22 R 15W
 BOOK PAGE 18 LINE 6

State of KANSAS }
 County of SENECA } SS:

I, E. W. Fisher of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the ACKERMAN #1 well.

(Handwritten signature)

Subscribed and sworn to before me this 10th day of March 19 54

My Commission Expires: October 13, 1954.

NOTARY PUBLIC