

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH

Locate well correctly on above
Section Plat

Reno County. Sec. 31 Twp. 23S Rge. 10 (E) W (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. C S $\frac{1}{2}$ NW/4 NE/4
Lease Owner. Stanolind Oil and Gas Co.
Lease Name. Ira C. Johnson Well No. 8
Office Address. Box 591, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole). Oil
Date well completed. January 28, 1945
Application for plugging filed. April 19, 1948
Application for plugging approved. April 20, 1948
Plugging commenced. May 3, 1948
Plugging completed. May 5, 1948
Reason for abandonment of well or producing formation. Depleted
If a producing well is abandoned, date of last production. April 7, 1948
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. Mr. C. D. Stough PBD 3732'
Producing formation. Viola Depth to top. 3678' Bottom. 3732' Total Depth of Well. 3770' Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Viola	Oil	3678'	3732'	13 3/8"	182'	None
				5 1/2"	3783'	3023'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from 3709' to 3675' feet to 190' to 160' feet for each plug set.
Filled with mud and rock from PBD 3732' to 3709'. Dumped 5 sacks cement, filled from 3709' to 3675'. Ripped casing at 2980' and pulled. Filled with mud from 3675' to 190'. Dumped 25 sacks cement, filled from 190' to 160'. Filled with mud from 160' to 20'. Dumped 15 sacks cement, filled from 20' to bottom of cellar.

5-14-48




(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to. Stanolind Oil and Gas Co.
Address. Box 518, Zenith, Kansas

STATE OF Kansas, COUNTY OF Stafford, ss.
Mr. C. B. Snyder (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. B. Snyder Field Superintendent
Box 518, Zenith, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of May, 1948
Paul Chadwick
Notary Public.

My commission expires 1-19-52 22-287 7-47-10M



FORMATION RECORD

DESCRIBE EACH FORMATION DRILLED. INDICATE THICKNESS, CONTENT AND WHETHER DRY, OR OIL, GAS, OR WATER BEARING.

FORMATION	TOP	BOTTOM	FORMATION	TOP	BOTTOM
Cellar	0	8			
Surface soil & sand	8	160			
Red Rock	160	190			
Red Bed	190	470			
Anhydrite	470	490			
Sand	490	510			
Red Bed	510	600			
Shale & Shells	600	860			
Shale, Shells & Salt	860	1215			
Shale and Shells	1215	1465			
Sand	1465	1490			
Shale and Shells	1490	1560			
Shale and Salt	1560	1585			
Shale and Lime	1585	1660			
Shale and Shells	1660	1770			
Sand	1770	1815			
Shale and Shells	1815	1940			
Shale and Lime	1940	2010			
Lime	2010	2160			
Shale	2160	2195			
Lime	2195	2270			
Shale	2270	2340			
Shale and Shells	2340	2430			
Shale	2430	2555			
Shale and Lime	2555	2645			
Shale	2645	2825			
Lime	2825	3130			
Lime and Shale	3130	3235			
Lime	3235	3420			
Lime & Chat	3420	3460			
Lime	3460	3678			
Top Misener	3677				
Top Viola	3678				
Lime	3678	3685			
Cherty Lime	3685	3687			
Cherty Lime	3687	3692			
Dolomite	3692	3699			
Dolomite	3699	3709			
Lime & Dolomite	3709	3712			
Dolomite & Lime	3712	3724			
Lime	3724	3729			
Lime & Chert	3729	3770			
Total Depth	3770				
Date of First Work:	December 10, 1945				
Drilling Started:	January 11, 1945				
Drilling Completed:	January 28, 1945				
First Production:	February 13, 1945				
Well Completed:	February 14, 1945				