


15-55-20047-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plot

Reno County, Sec. 31 Twp. 23 Rgs. 10 (E) (W)
Location as "NE/CNWKSW" or footage from lines
Lease Owner Stelbar Oil Corporation
Lease Name Johnson #1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 4/15/76 _____ 19____
Plugging completed 4/26/76 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3778 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	245	none
				5 1/2"	3756	2547'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, ran sand to 3700' and dumped 5 sacks cement.
Loaded hole with 80 barrels water, shot pipe at 3006', 2916', 2817', 2725', fluid went away. Loaded hole, shot pipe at 2626', 2529', pulled 81 joints of 5 1/2" casing. Allied pumped 5 sacks hulls, 25 sacks gel and 100 sacks cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC. 5-6-76
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
NOEL J. KNIGHT ss.


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

Subscribed and Sworn to before me this 28th day of April, 1976

My commission expires _____
NOTARY PUBLIC
MARGARET MELCHER
Rice County, Ks.
My Comm. Exp. Feb. 15, 1979

Margaret Melcher
Notary Public.



December 18, 1968

ARTH HOGAN - HOGAN PUBLIC

Handwritten signature

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas, this 18th day of February, 1968.

H. J. Plourde, President

Handwritten signature

I, H. J. Plourde, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Johnson #1, located on the South Unit, Tract #11, in the C-2 1/2 NE/4 of Sec. 31-23-10N, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.

CERTIFICATE

Measurements taken from K.D.

TOPSI

19, 1968.
Cut 12 1/4 in. hole to 243 ft. and run 245.85 ft. of 5/8 in. surface pipe and cemented with 250 sacks cement on bottom at 243 ft. Plug down at 12:30 P.M., February 12, 1968. Cut 2 7/8 in. hole to 275 ft. Run 278 ft. of 1 1/2 in. O.D. casing and set on bottom at 275 ft. with 100 sacks water saturated foam. Plug down at 1:30 P.M., Feb. 19, 1968.

0	to	175	Sand
175	to	243	Redd
243	to	1300	Shale & Shale
1300	to	2095	Line & Shale
2095	to	2800	Shale & Line
2800	to	2920	Line & Shale
2920	to	3120	Line
3120	to	3259	Sand & Shale
3259	to	3330	Line & Shale
3330	to	3535	Line
3535	to	3714	Shale & Line
3714	to	3758	Line
3758	to	3758	Line

ELEVATION:

COMPLETED: February 19, 1968

COMMENCED: February 10, 1968

LOCATED: C-2 1/2 NE/4, Sec. 31-23-10N, Reno County, Kansas

FARM: JOHNSON #1

CONTRACTOR: BLACKSTONE DRILLING, INC.

COMPANY: INDEPENDENT LEASE MANAGEMENT COMPANY

February 20, 1968

67460 McPHERSON • KANSAS

Box 455 - 523 West Kansas - Phone CH 1-1230

Blackstone Drilling, Inc.

