

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-145-21479-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate sp or completion date

WELL OPERATOR: RAMA Operating Co., Inc. KCC LICENSE # 3911
(owner/company name) (operator's)

ADDRESS: P.O. Box 159 CITY: Stafford
STATE: Kansas ZIP CODE 67578 CONTACT PHONE: 316-234-5191

LEASE: Galliant WELL#: 1-31 Section 31 Township 22s Range 15w
C E/2 Se Ne SPOT LOCATION/QQQQ COUNTY: Pawnee

3300 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)
400 FEET (in exact footage) FROM East LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS _____
SURFACE CASING SIZE 8-5/8" SET AT 534' KB _____ 340 SACKS _____
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS _____

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 2007 G.L. _____ 2016 K.B. _____ T.D. 3980 P.B.T.D. _____ Anhydrite Depth 946'-961'
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Received plugging orders from Scott Alberg at 11:10 am. 2-19-02. Plugged well as follows:
Heavy mud in hole. Used 60/40 Poz with 6% Gel. 1st plug: 50sx at 975'. 2nd plug: 50sx at 560'.
Top plug: 10 sx at 40', cemented to surface. Rathole 15sx. No mousehole. Plugging completed
at 11:45 am on 2-20-02 by Allied, ticket # 7577. Reported to KCC-Mike Maier 12:00 pm 2-20-02

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Name: Gary Pugh/Gary M. Talbott Phone#: (316) 672-9508

Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142
(company name) (contractor's)

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 11:45 am on February 20, 2002.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: _____ Operator X Agent _____

DATE: 02/20/02 AUTHORIZED OPERATOR OR AGENT FEB 26 2002 Gary M. Talbott
(signature) Gary M. Talbott, Agent for Operator

CONSERVATION DIVISION

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

Galliat 1-31

LOCATION: C E/2 Se Ne	Section 31 T 22s R 15w
API: 15-145-21479-00-00	Pawnee County, Kansas

OWNER: RAMA Operating Co., Inc.
CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 11-Feb-02
COMPLETED: 20-Feb-02

TOTAL DEPTH: **DRILLER** 3980 FEET
LOGGER 3983 FEET

Ground Elevation: 2007
KB Elevation: 2016

LOG

0 -	2 FEET	Top Soil
2 -	15 FEET	Clay
15 -	173 FEET	Sand and Gravel
173 -	310 FEET	Shales
310 -	538 FEET	Sand
538 -	946 FEET	Shales and Sand
946 -	961 FEET	Anhydrite
961 -	1981 FEET	Salt and Shale
1981 -	3980 FEET	Limestone/Shale and Dolomite

CASING RECORDS

Surface/Production Casing Data:
Spud @ 10:00 am on 02-11-02. Drilled 12 1/4" hole to 538'. Ran 13 joints of new 23# 8-5/8" surface casing, tallied 526.70' set at 534' KB. Cemented with 340 sacks 60/40 Poz, 2% Gel, 3% CC.
Plug down at 12:45 am on 02-12-02 by Allied. Good returns. Ticket # 08521.

PLUGGING RECORDS

Received plugging orders from Scott Alberg at 11:10 am. 2-19-02. Plugged well as follows:
Heavy mud in hole. Used 60/40 Poz with 6% Gel. 1st plug: 50sx at 975'. 2nd plug: 50sx at 560'.
Top plug: 10 sx at 40', cemented to surface. Rathole 15sx. No mousehole. Plugging completed at 11:45 am on 2-20-02 by Allied, ticket # 7577. Reported to KCC-Mike Maier 12:00 pm 2-20-02

DEVIATION SURVEYS

1/4 degree(s) at	538	feet
1/2 degree(s) at	2004	feet
3/4 degree(s) at	2908	feet

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 26 2002

CONSERVATION DIVISION