

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-145-20,319-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Columbian Resources Corporation OPERATOR'S LICENSE NO. 3517 8/91

ADDRESS Bank IV Tower Box 3501 Topeka, KS 66601-3501 PHONE # (913) 234-0581

LEASE (FARM) Barstow WELL NO. 1 WELL LOCATION NE NE SW COUNTY Pawnee

SEC. 25 TWP. 22S RGE. 15W (E) or (W) TOTAL DEPTH 4065 PLUG BACK TD 4031

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 498 CEMENTED WITH 350 SACKS

CASING SIZE 5 1/2 SET AT 4064' CEMENTED WITH _____ SACKS

PERFORATED AT 3696-3702 3738-44

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING WE WILL PLUG WELL ACCORDING TO THE RULES AND REGULATIONS OF THE STATE OF KANSAS.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? _____
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Stan Brady

PHONE # (913) 234-0581

ADDRESS Same As Above

PLUGGING CONTRACTOR Kelso Casing Pulling, Inc. LICENSE NO. 6050 6/91

ADDRESS P.O. Box 347 Chase, KS. 67524 PHONE # (316) 938-2943

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: _____

(Operator or Agent)

DATE:

5/10/90

F & M OIL, INC.

#1 BARSTOW

25-22-15W
NE NE SW

603 UNION CENTER, WICHITA, KS.

CONTR DUKE DRILLING CO.

CTV PAWNEE


GEOLOGIST GENE FALKOWSKI

FIELD NO. MC POINT VIEW DISC

1998 KB, C/J 13/74 ^{CARD} ISSUED 9/12/74 IP P 115 BOPD, NW

LANS 3696-44 OA

API 15-145-20, 319-0000



SMP	TOPS	DEPTH	DATUM
SC		925	+1073
YOH		2072	- 74
CO GR		2285	- 287
NEVA		2461	- 463
TARK		2842	- 844
HOW		2981	- 983
TOP		3050	-1052
HEEB		3434	-1436
YOR		3456	-1458
DOUG		3473	-1475
BR LM		3557	-1559
LANS		3565	-1567
SIMP SH		3990	-1992
ARB		4041	-2043
RTD		4065	-2067

INDEPENDENT OIL & GAS SERVICE

8-5/8" 498/350SX, 5 1/2" 4063/125SX

NO LOG

DST (1) 2847-2900/30-30-45-30, REC 154'

SL G THIN M, 434' SL GC WTR, BHP
966-926#, FP 34-292#

DST (2) 3561-80/20-20-20-20, 15' M,

BHP 895-799#, FP 15-23#

DST (3) 3595-3645/30-30-30-30, REC

251' M, BHP 1150-1118#, FP 47-158#

DST (4) 3685-3700/30-30-30-30, 240' V

HOCH, 120' FROTHY OIL, BHP 966-
918#, FP 31-118#

DST (5) 3708-50/45-30-30-30, 110' OCM;

60' OC THIN M, BHP 1070-1070#, FP
31-335#

DST (6) 3754-3800/45-30-60-45, REC 5'

HO&GCW, 320' GSY WTR, BHP 1198-

RECEIVED

OCT 13 1983

15-145-20319-0000

F & M OIL, INC.

#1 BARSTOW

25-22-15W
NE NE SW

1182#, FP 47-181#
MICT - PF 24/3738-44, 24/3696-3702, SET TUBING/PKR @ 3710, FU
980/12HRS, FROM 3696-3702, SWB 1/2 BOPH/TR W NAT, RE-SET PKR & SWB
3/4 BOPH NW, FROM 3739-44, 1000 ACID, CHANNELLED, RE-ACIDIZED
W/1000 ACID, PULLED TBG & PKR, REC LD & SWB 7380, NW/1-3/4HRS,
POP

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1989

CONSULTATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATICⁿ COMMISSION

OCT 13 1980

CONTRACTS DIVISION
WICHITA, KANSAS

BARSTOW No. 1
NE 1/4 SW Sec 25-22S-15W
Pawnee Co., KS

8 5/8" @ 498' W/350 SX

RECEIVED
STATE CORPORATICⁿ COMMISSION
OCT 13 1980
CONTRACTS DIVISION
WICHITA, KANSAS

TOP CMT @ 3465' W/150 SX (EST.)

AW 5 3565'

Pf 3 3696-3702'

Pf 5 3738-44'

Blkc 5800'

Arb 4041'

PB TO 4031'

5 1/2" @ 4065' W/150 SX

T.D. 4065'

No. R 2470 10 19 09 10 Sps to Inch Census Section - M. K. H. L. S. A.

VERBON HOLDING INC. LUTHER IN. N. J. 07206



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
JACK SHRIVER COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

July 17, 1990

Columbian Resources Corporation
Bank IV Tower, Box 3501
Topeka, KS 66601-3501

Barstow #1
NE NE SW 25-22-15W
Pawnee County, KS
API No. 15-145-20,319-0000

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
Production Supervisor

District: #1, 304 W. McArtor
Dodge City, KS 67801