

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-009-03166-0000
API NUMBER 10-11-52

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Hitschmann Est.

WELL NUMBER 8

SPOT LOCATION NW NW SW

SEC. 32 TWP. 16 RGE. 11 EX. (W)

COUNTY Barton

Date Well Completed 10-11-52

Plugging Commenced 7-10-85

Plugging Completed 7-10-85

LEASE OPERATOR NCRA

ADDRESS Box 6, Great Bend, Ks. 67530

PHONE # (316) 793-7824 OPERATORS LICENSE NO. 5565

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hay, Ks.

Is ACO-1 filled? No If not, is well log attached? Yes

Producing formation Arbuckle Depth to top _____ bottom _____ T.D. 3366'

Shoe depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	279'	-0-
				5 1/2"	3363'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.


BJ-Titan Sery. Co. - Pumped 15 sx. cement down 5 1/2" x 8 5/8" Annulus
- Press. 300# - Pump 4 sx. hells - 25 sx. cement - 20 sx. Gel -
1 sx. hells - Release plug - 130 sx. cement - Max. press. 1500#
Shut in @ 1100#. Complete @ 11:45 a.m. 7-10-85.
All cement 60/40 Pozmix 6% Gel 3% CaCl.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor None License No. _____
Address _____

STATE OF KANSAS COUNTY OF BARTON, ss.

I. J. Gotsche (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) [Signature]
(Address) Box 6, Great Bend, Ks. 67530



STATE CORPORATION COMMISSION

My Commission expires: January 29, 1989

15 1985

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 12th day of July, 1985.

Patricia Schultz
Notary Public

Patricia Schultz

Form CP-4
114V 440 06-83


File
COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company NATIONAL COOPERATIVE REFINERY ASSOCIATION SEC. 32 T. 16 R. 11W
Farm Hitschmann Est. No. 8 NW NW SW

Total Depth. 1367
Cm. 9-11-52 Comp. 9-22-52
Shot or Treated.
Contractor. Birmingham-Bartlett Drlg Co.
Issued. 11-8-52

County Barton
KANSAS



CASINO:
8 5/8" 279' cem w/150 sx
5 1/2" 3363' cem w/100 sx

Elevation. 1921

Production. I.P. 40 bbls / 75%
water

Figures Indicate Bottom of Formations.

surface, post rock	80
shale	180
sand	210
shale, shells	585
shale red bed	780
anhydrite	810
shale, shells	1350
lime broken	1675
lime, shale	2080
shale, shells	2655
lime, shale	2860
lime	2980
lime, shale	3015
cored	3036
shale	3075
lime brown	3089
lime	3367
total depth	

Tops: Scout	
Anhydrite	780
Heebner	2974
Toronto	2987
Douglas	3017
Brown Lime	3074
Lansing	3089
Arbuckle	3362

K. G. S. LIBRARY

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1935

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1935

CONSERVATION DIVISION
Wichita, Kansas