

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- 145-20, 783-0000 ✓

245 North Water
Wichita, KS 67202

Operator's Full Name H.C. OIL EXPLORATION, INC.

Complete Address 8600 WEST 63RD # 305 SHAWNEE MISSION, KANS.

Lease Name BENNETT Well No. #1

Location NE-NW-SW Sec. 33 Twp. 22 Rge. 17 (East) (West)

County PANNEE Total Depth 4376 ^{FEET}

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor WHITE & ELLIS DRILLING INC. (BOB WASPER)

Address BOX 448 ELDORADO, KANSAS License No. _____

Operation Completed: Hour: 1:45 AM Day: 25TH Month: JAN Year: 19 81

The above well was plugged as follows:

8 5/8" 278 FEET SP. CUL. w/ 200ST 50/50 Pozmix 2% GEL. - 3% CH. CL.
ORDERED 115^{FEET} 50/50 Pozmix 4% GEL. + 8 5/8" PLUG. (ELV. 2065)
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS
1ST PLUG. @ 600 FEET w/ 65ST CNT.
2ND PLUG. @ 240 FEET w/ 30ST CNT.
3RD PLUG. → SOLID BRIDGE HULLS - PLUG. @ 40 FEET w/ 10ST CNT.
5^{FEET} IN RAT HOLE.
5^{FEET} IN ~~WATER~~ WATER WELL.

1-28-81

RECEIVED
CONSERVATION DIVISION
JAN 28 1981
CEMENTED BY SUR. CNT.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 2-26-81

INV. NO. 4710-W