

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-083-20,931-0000

LEASE NAME Bamberger "A" #2

WELL NUMBER _____

SPOT LOCATION C S/2 S/2 NE

SEC. 10 TWP. 22 SRGE. 23 W(E) or (W)

COUNTY Hodgeman

Date Well Completed 11/28/81

Plugging Commenced 2/27/85

Plugging Completed 3/4/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Raymond Oil Co., Inc.

ADDRESS One Main Place, Suite 900, Wichita, Ks. 67202

PHONE # (316) 267-4214 OPERATORS LICENSE NO. 5046

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4613'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	441'	none
				4 1/2"	4610'	2792'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 4550' & 4 sacks cement. Shot pipe @ 2792' & pulled 69 joints. Plugged well with 3 hulls, 15 gel, 70 cement, 10 gel, 1 hull, plug, and 125 sacks 60/40 poz 2% gel 3% c.c. Capped with ready-mix.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

APR 12 1985
4-12-1985
CONSERVATION DIVISION
Wichita, Kansas

COPY

SUBSCRIBED AND SWORN TO before me this 11th day of March, 1985

My Commission expires: _____



Irene Hoover
Notary Public