


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pawnee County, Sec. 28 Twp. 22 Rge. (E) 16 (W)
Location as "NE/CNW&SW" or footage from lines SW SW NE/L
Lease Owner M. B. Armer
Lease Name Peters Well No. 1
Office Address 710 Petroleum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed Feb. 4, 19 54
Application for plugging filed Feb. 4, 19 54
Application for plugging approved Feb. 4, 19 54
Plugging commenced Feb. 4, 19 54
Plugging completed Feb. 4, 19 54
Reason for abandonment of well or producing formation Dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1170 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	230'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy Rotary Mud to 220 ft.
set plug and cemented with 20 sacks cement
through drill pipe. Mudded to 40 ft. set plug
and cemented with 10 sacks cement to the surface.

2-11-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Armer, Inc.
Address 710 Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
L. C. Sponenberg (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

(Address) _____

SUBSCRIBED AND SWORN to before me this 10th day of February, 19 54

My commission expires February 13, 1956.

Rose Lurey Notary Public.

24-7368-5 3-53-20M
PLUGGING
FILE SEC 28 T 22 R 16 W
BOOK PAGE 12 LINE 11

15-145-01011-0000


KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **M. B. Armer**
FARM **Peters** NO. **1**

SEC. **28** T. **22S** R. **16W**
LOC. **SW SW NE**

TOTAL DEPTH **4170**
COMM. **1/22/54** COMP. **2/5/54**
SHOT OR TREATED
CONTRACTOR **Armer, Inc.**
ISSUED

COUNTY **Lawrence**
KANSAS



CASING
20 10
15 8 **230'**
12 6
13 5

ELEVATION **2049 K.B.**
PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	105
Blue Shale & Shells	230
Shale & Shells	280
Sand & Red Bed	702
Red Bed & Shells	1035
Anhydrite	1065
Shale & Shells	1890
Lime & Shale	2000
Lime - Broken	2125
Lime & Shale	2670
Shale & Shells	2855
Lime & Shale	3095
Shale	3150
Lime - Broken	3215
Lime & Shale	3385
Shale	3450
Shale & Shells	3480
Lime	3600
Shale & Lime	3655
Lime	3940
Lime & Shale	4055
Chert	4070
Shale	4100
Shale & Lime	4140
Lime	4170

FORMATION TOPS (K. B. Meas.)

HEERNER	3527
BROWN LIME	3640
LANSING-K.C.	3648
VIOLA	4041
SIMPSON	4070
ARBUCKLE	4130

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER, INC.

By *L.P. Spruisky*

STATE OF KANSAS
COUNTY OF SEDGWICK SS:

Subscribed and sworn to before me, a notary public, in and for said County and State this 10th day of February, 1954.

Robt. Lusey
Notary Public

My Commission expires February 13, 1956.

PLUGGING
FILE SEC 28 T 22 R 16 W
COOK PAGE 12 LINE 11