


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-145-00490-0000

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pawnee County, Sec. 28 Twp. 22 Rge. 16 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NE NW
Lease Owner DUNNE-GARDNER DRILLING CO., INC.
Lease Name Wilcox Well No. 1
Office Address 300 Schweiter Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 31, 1960
Application for plugging filed July 31 1960
Application for plugging approved July 31 1960
Plugging commenced July 31 1960
Plugging completed July 31 1960
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4120 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		0'	237'	8 5/8	7-18-60	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavymud to 237 feet - set plug,
1/4 sack of hulls and 20 sacks cement. Filled surface
pipe with heavy mud to 35 feet - set plug, 1/4
sack of hulls and 10 sacks of cement to surface
Put 5 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Don Gardner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
300 Schweiter Building, Wichita 2, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of August, 1960

My commission expires 12-14-61

[Signature]
Martha Gorges Notary Public.

DRILLER'S LOG

OPERATOR: Dunne-Gardner Drilling Co., Inc.
 300 Schweiter Building
 Wichita, Kansas

LEASE: Wilcox

WELL: No. 1

LOCATION: NW NE NW Section 28, Township 22 South,
 Range 16 West, Pawnee County, Kansas

DATE COMM: July 18, 1960

DATE COMPL: July 29, 1960

CASING: Set 8 5/8" casing @ 237' with 175 sacks of cement

<u>FROM</u>	<u>TO</u>	
0	237	Surface hole
237	275	Shale
275	495	Shale & Red Bed
495	600	Sand
600	1028	Red Bed
1028	1050	Anhydrite
1050	1930	Shale-Shells
1930	2515	Lime-Shale
2515	2800	Shale-Shells
2800	3520	Lime-Shale
3520	3560	Lime
3560	3700	Lime-Shale
3700	3757	Lime
3757	4010	Lime-Shale
4010	4045	Lime, Shale -Cherty Lime
4045	4055	Lime-Shale
4055	4079	Lime-Shale-Sand
4079	4120	Lime
	4120	T.D.
		D.&A.

RECEIVED
 STATE CORPORATION COMMISSION

AUG 8 1960

CONSERVATION DIVISION
 Wichita, Kansas

I certify the above to be true and correct to the best of my knowledge and belief.

DUNNE-GARDNER DRILLING CO., INC.

By Don Gardner
 Don Gardner

Subscribed and sworn before me this 4th day of August, 1960

Martha Gorges
 Martha Gorges, Notary Public

My commission expires:
 December 14, 1961