


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 28 Twp. 22S Rge. 16W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW SW SW
Lease Owner Alpine Drilling Co., Inc.
Lease Name Horning Well No. 1
Office Address 800 Bitting Building, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 7-17 1978
Application for plugging filed 7-17 1978
Application for plugging approved 7-17 1978
Plugging commenced 7-17 1978
Plugging completed 7-17 1978
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4141
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Plugged hole 7-17-78; Filled hole w/rotary mud, pumped 50 sx cement thru
open end D.P. @ 420'; mud to 240'; pumped 25 sx cement thru open end D.P.;
mud to 40'; 1/2 sx hulls & wood plug for solid bridge; pumped 10 sx to
base of cellar - used 50/50 pozmix w/2% gel; 2 sx in rathole; completed
@ 3:00 a.m. by Allied;

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1978 7-21-78

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wichita, Kansas


STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Jon T. Williams, Jr. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) *Jon T. Williams, Jr.*
800 Bitting Bldg., Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of July, 1978

Geraldine Stewart
Geraldine Stewart Notary Public.

My commission expires January 12, 1981





800 Bitting Bldg
 Wichita, Kansas 67202
 Phone 316 - 263-7904
 Mobile Phone 316 - 793-7859 Unit 7070

July 19, 1978

WELL LOG-----HORNING NO. 1

Located: SW SW SW of Sec. 28-22S-16W, Pawnee
 County, Kansas.

OWNER: Alpine Drilling Co., Inc.
 ROTARY CONTRACTOR: Husky Drilling Co., Inc.

COMMENCED: 7-10-78
 COMPLETED: 7-17-78

TOTAL DEPTH: 4141'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 526 Shale	Ran 7 jts., 8-5/8", 28#, 8V, Rge 3,
526 - 588 Sand	used csg. - tallied 286.13, set
588 - 1044 Shale & Sand	293 KB w/225 sx common 2% gel, 3%
1044 - 1075 Anhydrite	cc - circulated - plug down @
1075 - 1224 Shale	8:15 p.m. by Allied.
1224 - 2313 Shale & Shells	
2313 - 3641 Shale & Lime	
3641 - 3790 Lime	
3790 - 4025 Lime & Shale	
4025 - 4090 Lime	
4090 - 4124 Lime & Shale	
4124 - 4141 Lime	Plugged 7-17-78

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 21 1978
 CONSERVATION DIVISION
 Wichita, Kansas