

15-145-20416-0000

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 23 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Alpine Drilling Co., Inc.

Complete Address 800 Bitting Bldg., Wichita, Kansas

Lease Name Chesky Well No. 1

Location C NE NE Sec. 33 Twp. 22 Rge. (E) (W) 16

County Pawnee Total Depth 4160'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Sterling Drlg.

Address Sterling, Kansas License No.

Operation Completed: Hour 8 A Day 18 Month 2 Year 1976

The above well was plugged as follows:

RTD 4160' 8 5/8 csg set 293' cwc 180 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 400' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ken L. Massey
Well Plugging Supervisor

DATE 2-25-76

INV. NO. 2771-W