

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Ehrlich Drilling Company
Complete Address Box 338 Wilson, Kansas 67490
Lease Name Cheskey Well No. 1
Location NW NW NW Sec. 33 Twp. 22 Rge. (E) (W) 16
County Pawnee Total Depth 4145'
Abandoned Oil Well XX Gas Well XX Input Well SWD Well D & A X
Other well as hereafter indicated Oil string set. Completed DA
Plugging Contractor Glenn & Smith Pipe Pulling
Address Box 156 Ellinwood, Kansas License No. 396
Operation Completed: Hour 3:30 P Day 20 Month 1 Year 1971

The above well was plugged as follows:

Total Depth 4145' 8 5/8 csg set at 2601' cwc

5 1/2 csg set at 4145' cw 125 sk cmt.

5 1/2 csg perf. (4064')

Filled 5 1/2 csg W/sd (4000-4145) Dumped 5 sk cmt W/dump bailer. (3960-4000)

Recovered 2225' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel W/3 sk hulls, release plug and pumped 100 sk

40-60 poz 2%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 1/25/71INV. NO. 3250-u