

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

JAN 24 1977  
1-24-77

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-145-20,448-0000 (of this well)

Operator's Full Name White & Ellis Drlg., Inc.

Complete Address Box 448, El Dorado, Kansas

Lease Name Vratil Well No. 1

Location C W/2 NW SW Sec. 33 Twp. 22 Rge. (E) (W) 16

County Pawnee Total Depth 4190'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Woodman-Iannitti Drlg.

Address Hosington, Kansas License No.       

Operation Completed: Hour 11:45 A Day 22 Month 1 Year 1977

The above well was plugged as follows:

RTD 4190' 8 5/8 csg set 338' cwc 225 sx. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 420' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Leo Massey  
Well Plugging Supervisor

DATE 1-24-77

INV. NO. 4522-61