

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-079-20644-0000

API NUMBER 4390

LEASE NAME Schmidt L

WELL NUMBER I

2310 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 29 TWP. 22 RGE. 3 (E) or (W)

COUNTY Harvey

Date Well Completed 4-3-90

Plugging Commenced 8-7-00

Plugging Completed 8-9-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

LEASE OPERATOR Lachenmayr Oil Co.

ADDRESS 904 Emmaline Newton, KS 67114

PHONE (316) 283-2660 OPERATORS LICENSE NO. 6804

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation Simpson Depth to Top _____ Bottom _____ T.D. 3790

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				13 3/8	257	0
				8 5/8	658	0
				5 1/2	3786	1492

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set

Set bottom bridge at 3700' Dump 5 sacks. Start pipe at 1492'. Pull to 700' Pumped 50 sacks. Pulled to 310' Cement to surface.

Name of Plugging Contractor K. E. Snyder Co. LLC License No. 32147

Address Hamilton, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lachenmayr Oil Co.

STATE OF Kansas COUNTY OF Harvey, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) _____


SUBSCRIBED AND SWORN TO before me this 27th day of September, 2000

BERNICE CAPPS
NOTARY PUBLIC
STATE OF KANSAS
My Appl. Exp. _____

My Commission Expires: August 4, 2002

Notary Public

Form 824
Revised 05-81



WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Lachenmayr Oil Co., 1103 N. Main, Newton, KS 67114

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
Wichita, Ks. 67202

Lease Name Schmidt "L" Well No. 1

Sec. 29 T. 22 S R. 3 W Spot SW/4

County Harvey State Kansas Elevation _____

Casing Record:

Surface: 13 3/8" @ 257' with 235 3% CC 2% Gel
8 5/8"@ 658' with 375 3% CC sx.

Production: 5 1/2"@ 3783' with 190 sx.

Type Well: Oil Well Total Depth 3786'

Drilling Commenced 4-3-90 Drilling Completed 4-15-90

Formation	From	To	Tops
Cellar	0	7	
Shale	7	475	
Shale, Lime	475	550	
Lime, Shale	550	664	
Shale, Lime	664	800	
Shale	800	1031	
Shale, Lime	1031	1863	
Sand	1863	1882	
Shale, Lime	1882	2200	
Sand	2200	2395	
Shale	2395	2499	
Lime	2499	2575	
Shale, Lime	2575	2712	
Shale	2712	2721	
Lime	2721	2960	
Shale, Lime	2960	3046	
Shale	3046	3147	
Shale, Lime	3147	3210	
Lime	3210	3478	
Shale	3478	3585	
Lime	3585	3650	
Shale	3650	3734	
Sand	3734	3786	

APR 25 1990

CONSERVATION DIVISION
Wichita, Kansas