

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

10001-0001

API NUMBER 15-079-01,001

LEASE NAME Schmidt "A" "OWWO"

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1

4290 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 29 TWP. 22S RGE. 3 ~~XXXX~~ (W)

COUNTY Harvey

Date Well Completed 12-18-90

Plugging Commenced 12-18-90

Plugging Completed 12-18-90

LEASE OPERATOR Lachenmayr Oil Company

ADDRESS 1103 N. Main, Newton, KS 67114

PHONE#(316) 283-2660 OPERATORS LICENSE NO. 6804

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-18-90 (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well loc. attached? No

Producing Formation N/A Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3820'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size          | Put In | Pulled out  |
|-----------|---------|------|----|---------------|--------|-------------|
|           |         |      |    | <u>8 5/8"</u> |        | <u>None</u> |
|           |         |      |    |               |        |             |
|           |         |      |    |               |        |             |
|           |         |      |    |               |        |             |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spotted 35 sx. cement @ 3815' (top of Arbuckle) thru drill pipe.  
Spotted 35 sx. cement @ 380' thru drill pipe.  
Spotted 25 sx. cement @ 60' thru drill pipe. 10 sx. cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc.

License No. 5420

Address 401 E. Douglas, Suite 500, Wichita, Ks. 67202

RECEIVED  
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: \_\_\_\_\_

DEC 25 1990 12-26-90

STATE OF Kansas COUNTY OF Sedgwick, ss.

CONSERVATION DIVISION

Michael L. Considine (Employee of White & Ellis Drilling, Inc. or Conservation of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael L. Considine


(Address) 401 E. Douglas, Suite 500, Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 21st day of December, 19 90

My Commission Expires: \_\_\_\_\_

CAROLYN J. TJADEN  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. Sept. 5, 1992

Notary Public



29 22 3W

15-079-10001-0001

# WHITE

AND ELLIS DRILLING, Inc.

## DRILLERS LOG

OPERATOR: Lachenmayr Oil Co., 1103 N. Main, Newton, KS 67114

CONTRACTOR: White & Ellis Drilling, Inc. 401 E. Douglas - Suite 500  
Wichita, Kansas 67202

Lease Name Schmidt "A" Well No. 1 "OWWO"

Sec. 29 T. 22S R. 3W Spot SW NE NW

County Harvey State Kansas Elev. \_\_\_\_\_

### Casing Record:

Surface: 8 5/8" @ \_\_\_\_\_ with \_\_\_\_\_ sx.

Production: \_\_\_\_\_ @ \_\_\_\_\_ with \_\_\_\_\_ sx.

Type Well: D & A Total Depth 3820'

Drilling Commenced 12-15-90 Drilling Completed 12-18-90

| Formation      | From | To   | Tops      |      |
|----------------|------|------|-----------|------|
| Cellar         | 0    | 7    | Maquoketa | 3670 |
| Cement & Plugs | 7    | 220  | Viola     | 3705 |
| Open Hole      | 220  | 3135 | Simpson   | 3740 |
| Lime           | 3135 | 3670 | Arbuckle  | 3815 |
| Shale          | 3670 | 3705 |           |      |
| Lime           | 3705 | 3740 |           |      |
| Sand           | 3740 | 3820 |           |      |

STATE

DEC 28 1990

CONSERVATION DIVISION  
Wichita, Kansas

DEC 28 1990