

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Harvey SEC. 28 TWP. 22S RGE. 3W E/W  
Location as in quarters or footage from lines:  
680' FWL and 380' FSL


Locate Well  
correctly on above  
Section Platt.

Lease Owner Harold J. Milburn (Oil & Gas Producers)  
Lease Name Adrian "B" #1 Well No. \_\_\_\_\_  
Office Address 7315 N. Monroe, Hutchinson, Ks. 67501  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 3/27/81  
Plugging completed 4/2/81  
Reason for abandonment of well or producing formation \_\_\_\_\_

\_\_\_\_\_ Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3270'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	276'	None
				4-1/2"	3250'	2209'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved in. Ran sand to 3200' and set 4 sacks cement. Made shots at ~~XXXX~~ 2804, 2654, 2529 and 2224. Pulled total string of 57 joints. Plugged well with 4 sacks hulls, 10 sacks gel and 100 sacks cement 50/50 pos 2% gel. Plugging complete.

RECEIVED  
STATE CORPORATION COMMISSION

APR - 7 1981

4-7-81

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor ~~XXXXXXXXXXXX~~ KELSO CASING PULLING Wichita Kansas  
CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April, 1981

My Commission expires:



Joan Kelso  
Notary Public.

KANSAS DRILLERS LOG

COMPANY Harold J. Milburn  
FARM Adrian "B" NO. 1

SEC. 28 T. 22S R. 3W  
LOC. 680' FWL & 480' FSL

COUNTY Harvey

ROTARY TOTAL DEPTH 3,270'  
COMM. August 5, 1980 COMP. August 10, 1980  
CONTRACTOR H-30, Inc. (Rig #7)  
ISSUED August 25, 1980

CASING

10 3/4"  
8 5/8" Set at 276' cemented w/250 sxs cement  
5 1/2"  
4 1/2" Set at 3,250' cemented w/75 sxs cement

ELEVATION 1,439' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	110'
Sand and Shale	280'
Shale	339'
Shale, Shells and Lime	840'
Shale and Lime	1,410'
Lime and Shale	3,266'
Lime	3,270'
Rotary Total Depth	3,270'

I hereby certify the above and foregoing to be  
a true and correct log of the above described  
well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
Dean Britting

State of Kansas )  
                          ) ss:  
County of Sedgwick )

Subscribed and Sworn to before me a Notary Public  
in and for said county and state this 25th day of  
August, 1980.

NOTARY PUBLIC COMMISSION  
MAR - 9 1981  
CONSERVATION DIVISION  
Wichita, Kansas

*Elsie Willison*  
Elsie Willison - Notary Public

My Commission Expires:  
July 25, 1982