

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Harvey County. Sec. 27 Twp. 22S Rge. 3W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NE/4


Lease Owner Vincent Oil Corporation  
Lease Name Lisenby #1 Well No. 1  
Office Address 901 Union Center, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole

Date Well completed August 15, 1977 19  
Application for plugging filed August 15, 1977 19  
Application for plugging approved August 15, 1977 19  
Plugging commenced 3:00 PM, August 15, 1977 19  
Plugging completed 5:00 PM, August 15, 1977 19  
Reason for abandonment of well or producing formation  
Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3290'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	211'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud.  
Pumped 35 sacks Regular cement to  
235' thru open end drill pipe, solid  
bridge at 40' with 1/2 sack hulls, Howco plugs  
15 sacks. 2 sacks in rathole.

8-18-77  
RECEIVED  
STATE CORPORATION COMMISSION  
AUG 18 1977  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING COMPANY, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.  
F. A. Wuellner (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner  
F. A. Wuellner, Secretary  
P. O. Box 129, Sterling, Kansas 67579  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of August, 19 77

Charles M. Hall  
Charles M. Hall, Notary Public.

My commission expires CHARLES HALL—NOTARY PUBLIC  
My Commission Expires Jan. 6, 1978



STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- LISINBY #1  
Located: NE/4, Section 27-22S-3W, Harvey County, Kansas.

OWNER: Vincent Oil Corporation  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: August 8, 1977  
COMPLETED: August 15, 1977

TOTAL DEPTH: 3290'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 216 Clay and Gravel, Shale	Ran 5 joints 10 3/4" OD casing, 199' pipe set at 211' K.B. Cemented with 240 sacks 60/40 Pozmix with 3% cc. Plug down at 10:30 PM, 8-8-77, by Howco.
216 - 605 Shale and Lime	
605 - 705 Shale	
705 - 2975 Lime and Shale	
2975 - 3250 Lime	
3250 - 3290 Mississippi	Plugged.