

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Hodgeman County, Sec. 24 Twp. 22S Rge. (E) 22(W)

Location as "NE/CNW/SW" or footage from lines G SW SE

Lease Owner Tilco, et al

Lease Name Ruff Well No. 1

Office Address 200 Sutton Place, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 23 19 69

Application for plugging filed October 23 19 69

Application for plugging approved October 23 19 69


Plugging commenced October 23 19 69

Plugging completed October 23 19 69

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Edger Eaves

Producing formation Depth to top Bottom Total Depth of Well 4510 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	332	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged @ 850 with 80 sacks cement, Plugged @ 330' with 30 sacks cement  
Bridged @ 40' with 10 sacks

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 31 1969  
CONSERVATION DIVISION  
Wichita, Kansas

10-31-69

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530


STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

Box 486, Great Bend, Kansas (Address)

Subscribed and sworn to before me this 30 th day of October, 1969

My commission expires April 1, 1971



Wanda Nichols  
Notary Public.

DRILLER'S LOG

COMPANY  
CONTRACTOR  
FARM  
LOCATION  
  
COMMENCED  
COMPLETED

TILGO, ET AL  
LEBEN DRILLING, INC.  
RUFF #1  
G SW SE SECTION 24-22S-22W  
HODGEMAN COUNTY, KANSAS  
10-14-69  
10-23-69

0 190  
190 333  
333 450  
450 550  
550 730  
730 745  
745 820  
820 1020  
1020 1379  
1379 1410  
1410 1900  
1900 2175  
2175 2390  
2390 2525  
2525 3745  
3745 4488  
4488 4490  
4490 4510  
4510

Shale  
Red Bed, Shale  
Shale  
Red Bed, Sandy Shale  
Red Bed, Shale  
Anhydrite  
Shale  
Sand  
Red Bed, Shale  
Anhydrite  
Shale, Shell  
Shale  
Shale, Lime  
Lime  
Lime, Shale  
Lime  
Chert, Lime  
Lime, Chert  
RTD

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 31 1969  
CONSERVATION DIVISION  
Wichita, Kansas

8 5/8" 20# new surface casing set @ 332' cemented with 250 sacks common 2% cc.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Ruff #1 Well, located G SW SE of Section 24, Township 22 South, Range 22 West, Hodgeman County, Kansas, as reflected by the records of Leben Drilling, Inc.

*Leslie Kite*  
\_\_\_\_\_  
Leslie Kite

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON )

Subscribed and sworn to and before me, a Notary Public, in and for Barton County Kansas, this 30th day of October, 1969.

*Ulanda Nichols*  
\_\_\_\_\_  
Ulanda Nichols

My Commission Expires:  
April 1, 1971

