



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1972
11-06-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Earl Bocker of N. C. R. A. has this
date requested permission to plug the following described well:

Mr. N. C. R. A. guarantees payment of the plugging fee.

Operator's full Name: National Cooperative Refinery Association

Complete Address: Box # 6, Great Bend, Kansas 67530

Lease Name: Hitschmann Estate Well No. # 7

Location: SE SW SW Sec. 32 Twp. 16 Rge. 11 (E)(W) W

County: Barton Total Depth 3377 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Comstock was instructed to plug the well as follows:

8 5/8" csg. 277' Cwc. Perf. 3021'.

Sanded hole back to 3000' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 2 sax hulls; 20 sax mud, 1 sax

hulls, & 100 sax cement with Allied Cementing Company's pump truck,

cementing from 345' to base of cellar.

Very truly yours,

Don Zurek
Conservation Division Agent